




FHWA REG. NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	SHEETS
7	KANSAS	STP-N012(901)	1999	95	131




FLAT PLATE STREET NAME SIGN



STREET NAME SIGN BLADE DETAILS




TYPICAL END OF ROADWAY SIGN MOUNTING INSTALLATION




TYPICAL TRAFFIC CONTROL SIGN MOUNTING INSTALLATION CURB AND GUTTER SECTION




DETAIL A 6 3/4" STANDARD



DETAIL B 9" METRO



TYPE I BARRICADE DETAIL W/ E.O.R. MARKER



TYPICAL STREET NAME SIGN MOUNTING INSTALLATION CURB AND GUTTER SECTION

STREET NAME	NO. BLADES REQ'D*	
	6 3/4" STD.	9" METRO
Pawnee 8500 E	1	1
Oak Knoll 2300 S	1	1
Pawnee 8700 E	2	2
Capri 2400 S	1	1
Dalton 2300 S	1	1
Pawnee 8800 E	3	3
Dalton 2400 S	1	1
Capri 2300 S	1	1
Linden 2400 S	1	1
Pawnee 9100 E	2	2
Cypress 2300 S	1	1
Cypress 2400 S	1	1
Pawnee 9300 E	1	1
Cooper 2300 S	1	1
Pawnee 9200 E	1	1
Cooper 2400 S	1	1
Pawnee 9300 E	1	1
Laurel 2400 S	1	1
Webb Rd 2400 S	1	1
Carson 9500 E	1	1
Webb Rd 2300 S	1	1
Pawnee 9500 E	1	1

* FOR INFORMATION ONLY - BID AS LUMP SUM

SIGN ASSEMBLY TABLE			
STATION	OFFSET	SIGN	QUANTITY*
Pawnee Ave.			
3+839	16 m Rt.	SNS	1
3+851	16 m Rt.	R1-1	1
3+870	9 m Rt.	W1-8	2
3+920	9 m Rt.	W1-8	2
3+970	9 m Rt.	W1-8	2
4+050	15 m Rt.	SNS	1
4+064	15 m Rt.	R1-1	1
4+070	9 m Lt.	W1-2R	1
4+114	15 m Lt.	R1-1	1
4+130	15 m Lt.	SNS	1
4+138	15 m Rt.	SNS	1
4+153	15 m Rt.	R1-1	1
4+190	9 m Lt.	R2-1(40)	1
4+190	9 m Rt.	R2-1(40)	1
4+237	15 m Rt.	SNS	1
4+238	15 m Lt.	R1-1	1
4+251	15 m Rt.	R1-1	1
4+254	15 m Lt.	SNS	1
4+540	15 m Rt.	SNS	1
4+541	15 m Lt.	R1-1	1
4+555	15 m Rt.	R1-1	1
4+557	15 m Lt.	SNS	1
4+659	15 m Rt.	SNS	1
4+670	15 m Lt.	R1-1	1
4+675	15 m Rt.	R1-1	1
4+687	15 m Lt.	SNS	1
4+775	15 m Rt.	SNS	1
4+788	15 m Rt.	R1-1	1
4+850	9 m Lt.	R2-1(40)	1
5+080	11 m Rt.	W4-2	1
5+148	9 m Rt.	R2-1(55)	1
Webb Rd.			
4+831	14 m Lt.	R1-1	1
4+845	14 m Lt.	SNS	1
4+924	11 m Lt.	W4-2	1
4+983	22 m Lt.	SNS	1
TOTAL			38

* FOR INFORMATION ONLY - BID AS LUMP SUM

NOTE: REFERENCES BELOW TO "STANDARD SPECIFICATIONS" DENOTE "STANDARD SPECIFICATION FOR STATE ROAD AND BRIDGE CONSTRUCTION EDITION 1990" BY THE KANSAS DEPARTMENT OF TRANSPORTATION.

- POST ANCHORS: POSTS SHALL BE ANCHORED WITH A YIELDING BASE POST SUPPORT AS DETAILED.
- POSTS FOR TRAFFIC CONTROL SIGNS: POSTS SHALL CONFORM TO THE REQUIREMENTS OF SUBSECTION 1620 OF THE STANDARD SPECIFICATIONS EXCEPT THAT ALL POSTS SHALL WEIGH 3 LBS./FOOT MINIMUM.
- POSTS FOR STREET NAME SIGNS (SNS): POSTS SHALL BE 9 FEET LONG, CONSTRUCTED FROM 2 3/8" O.D. GALVANIZED STEEL PIPE WEIGHING A MINIMUM OF 3 LBS./FOOT. POSTS SHALL BE POSITIONED SO THAT THE BOTTOM BLADE IS 7 FEET ABOVE GRADE.
- POSTS FOR END OF ROADWAY SIGN TO BE 8' LONG AND INSTALLED A MINIMUM OF 4' FROM ROADWAY TO BOTTOM OF SIGN.
- SIGN BLANKS FOR TRAFFIC CONTROL SIGNS: SIGN BLANKS SHALL BE FABRICATED FROM 0.080" ALUMINUM ALLOY 6063-T6 CONFORMING TO THE REQUIREMENTS OF SUBSECTION 1626 OF THE STANDARD SPECIFICATIONS.
- SIGN BLADES FOR STREET NAME SIGNS: EXTRUDED ALUMINUM BLADES SHALL BE ALUMINUM ALLOY CONFORMING TO 6063-T6 OR 5052-H38 (ASTM SPECIFICATION B221, LATEST ISSUE). BLADES SHALL HAVE AN ALODINE OR PHOSPHATE ETCHED FINISH. BLADES SHALL HAVE SQUARE CORNERS AND NO HOLES. MINIMUM BLADE LENGTH SHALL BE 24". MAXIMUM BLADE LENGTH SHALL BE 48". LENGTH VARIES BY INCREMENTS OF 6". BLADES BEARING THE STREET NAMES SHALL BE FIRMLY ATTACHED TO THE MOUNTING BRACKETS USING ALLEN-TYPE SET SCREWS. THE BLADES SHALL BE ORIENTED PARALLEL TO THE STREET.
- MOUNTING BRACKETS FOR SIGNS: DIE-CAST ALUMINUM BRACKETS SHALL BE ALUMINUM ALLOY 360 HAVING A TENSILE STRENGTH OF 44,000 PSI. THE BRACKETS SHALL BE SMOOTHLY FINISHED FREE OF PITS, BURRS, AND FLAWS. EACH BRACKET SHALL BE TAPPED AND DRILLED FOR 5/16" ZINC-PLATED ALLEN-TYPE SET SCREWS HAVING SELF-LOCKING SAW-TOOTH ENDS.
- FASTENERS: ALL STEEL FASTENERS FOR TRAFFIC CONTROL SIGNS SHALL BE GALVANIZED AND SHALL CONFORM TO THE REQUIREMENTS OF SUBSECTION 1614 OF THE STANDARD SPECIFICATIONS.
- REFLECTIVE SHEETING: REFLECTIVE SHEETING SHALL BE TYPE II - HIGH PERFORMANCE CLASS HA IN ACCORDANCE WITH SUBSECTION 2201 OF THE STANDARD SPECIFICATIONS.
- PROCESS INK: ALL PROCESS INK SHALL CONFORM TO THE REQUIREMENTS OF SUBSECTION 2202 OF THE STANDARD SPECIFICATIONS.
- DETAILS: REGULATORY AND WARNING SIGNS SHALL CONFORM TO THE DETAILS IN "STANDARD HIGHWAY SIGNS", FHWA, 1979.
- DETAILS - SNS: THE REFLECTIVE SHEETING FOR THE 6 3/4" STANDARD SIZE SNS IS TO BE THE HIGHWAY GREEN BACKGROUND WITH SILVER-WHITE #2 COPY WITH 4" UPPER CASE AND LOWER CASE PRIMARY COPY AND SUFFIX COPY. BOTH SERIES "C". FACES TO TRIM TO A 6 1/4". (SEE DETAIL A.)

THE REFLECTIVE SHEETING FOR THE 9" METRO SIZE SNS IS TO BE THE HIGHWAY GREEN BACKGROUND WITH SILVERWHITE #2 COPY WITH 5" UPPER CASE AND LOWER CASE PRIMARY COPY AND SUFFIX COPY, BOTH SERIES "C". THE CARDINAL DIRECTION CENTERED DIRECTLY BELOW THE BLOCK NUMBER SHALL BE AN UPPER CASE, 3" SERIES "C" LETTER. FACES TO TRIM TO A 8 1/2" WIDTH. (SEE DETAIL B.)

FOR CUL-DE-SAC STREETS, A 9" METRO SIZE BLADE SHALL BE USED WITH THE HOUSE NUMBERS DISPLAYED BENEATH THE STREET NAME. LETTERING TO BE THE SAME AS FOR THE 6 3/4" SIZE BLADE, EXCEPT THAT THE HOUSE NUMBER INFORMATION SHALL BE 4" SERIES "C".

SHOP DRAWINGS OF LAYOUT FOR SNS SHALL BE SUBMITTED TO THE TRAFFIC ENGINEERING DIVISION OF THE CITY OF WICHITA FOR APPROVAL PRIOR TO FABRICATION. THE FINISHED SIGNS AS SUPPLIED SHALL BE OF GOOD APPEARANCE, FREE FROM RAGGED EDGES, CRACKS SCALES OR BLISTERS AND SHALL BE CLEAN-CUT. SIGNS SHALL BE PACKED IN SUCH MANNER AS TO PREVENT DAMAGE OR DEFAACEMENT DURING SHIPMENT OR STORAGE.

- PERMANENT TRAFFIC CONTROL AND SNS: PERMANENT TRAFFIC CONTROL AND SNS SHALL BE MEASURED AND PAID FOR AT THE LUMP SUM PRICE FOR SIGNING. THE PAYMENT AS SET FORTH ABOVE SHALL BE CONSIDERED FULL COMPENSATION FOR ALL EXCAVATION, BACKFILLING, POSTS, ANCHORS, FASTENERS, MATERIALS, LABOR, TOOLS AND INCIDENTALS NECESSARY TO COMPLETE THIS WORK.

SIGNING DETAILS

SCALE: NONE APPROVED BY: DATE: AUG. 1999

DRAWN BY: TM REVISED: JUNE '97

CITY OF WICHITA
DEPARTMENT OF PUBLIC WORKS
TRAFFIC ENGINEERING SECTION SHEET 95 OF 131