FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87N-0128-01	.	23	118

DATE	BY	REFERENCES NOTED	REFERENCES CHECKED

REMOVE MEDIAL NOSE AND REPLACE WITH MOUNTABLE RAMP END.

REMOVE EXISTING MEDIAN. REPLACE WITH 200mm REINF. CRUSHED ROCK BASE; 130mm BM-2 BASE COURSE AND 50mm BM-2 SURFACE COURSE.

INSTALL 10.920M METAL HANDRAIL, CENTER ON INLET. SEE DETAILS SHEET 39

CONSTRUCT 1 800 SIDEWALK (AE) (100 mm) SEE TYPICAL SECTION SHEET 7.

P.V.I. Elev. 400.389 No V.C.

P.V.I. Elev. 400.200 No V.C.

-0.638%

5+291.674

5+321.296

GENTRY 4TH ADDITION

DENMARK 5-222.411

A.C. Pavement

COUNTRY ACRES 2ND ADDITION

20

9

8

7

4

WATER METER TO BE ADJUSTED

WATER VALVE TO BE ADJUSTED - MATCH WALK

200mm Water Service

Proposed 200mm Water

Exist. 500mm CI Water

450mm Son. Sewer

200mm CS Gas (KGS)

100mm CS Gas (PNG)

Exist. 200mm CI Water

600mm RCP

Exist. 200mm CI Water

375mm RCP

700 mm

SSMH

SWSMH Top=400.556

SWSMH Top=400.435

SWSMH Top=400.440

200mm RCP

450mm RCP

375mm RCP

RIDGE ROAD

+200

+300

400.399

400.279

Top=400.379 SSMH

Top=400.386 SSMH

Top=400.378 SSMH

200mm Son. Sewer

50mm Gas (PNG)

Exist. 200 Walk

Construction Limits

5+291.674 @ 600 Rt.

5+293.104 @ 748 Rt.

5+293.104

5+302.250

5+321.296

0.353

0.001

0.363

0.388

0.367

0.383

0.159

0.288

0.336

0.186

0.382

0.239

A.C. Pavement

Concrete Pavement

WATER METER TO BE ADJUSTED

CONSTRUCT 1 500 SIDEWALK (AE) (100 mm) SEE TYPICAL SECTION SHEET 7.

REMOVE EXIST. FLUME AS NEEDED FOR CONSTRUCTION. RECONNECT FLUME TO NEW CURB.

-0.722%

P.V.I. Elev. 400.353 No V.C.

P.V.I. Elev. 400.159 No V.C.

BOTTENBERG 2ND ADDITION

JOHNSON'S GARDEN CENTER

1

1

SRB

SCALE

5 0 5 10

PLAN: Lat. & Long. (meters)

RIDGE ROAD
STATION 5+175 TO 5+325 STATION

SRB 924 NORTH MAIN WICHITA, KANSAS 67203 http://www.feist.com/~srb 316-264-8008 FAX 264-4621 E-Mail: srb@feist.com

SAVOY, RUGGLES & BOHM, P. A. ENGINEERING & SURVEYING

PROJECT NUMBER 472-76-245-83057-000-000-001

DRAWN	DESIGN	REVIEW	DATE	UTILITY	SRB JOB
JRA	CMB/KWL		Dec. 13, 2000		1218T

REVISED

Doc. ID: Ridge_04 23 118