FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	-	-	67	118

BY	DATE
REFERENCES NOTED	
REFERENCES CHECKED	

Sta. 9+715.33, 13 22 Lt.
Install Junction Box.

Pull-Wire (#19 AWG) in 50mm RGC. Typical this sheet.

Sta. 9+769.34, 13 23 Lt.
Install Junction Box.

Sta. 9+817.22, 13 22 Lt.
Install Junction Box.

Sta. 9+871.26, 13 22 Lt.
Install Junction Box.

Sta. 9+921.80, 16 31 Lt.
Install Junction Box.

Sta. 9+976.10, 19 90 Lt.
Install Junction Box.

COUNTRY ACRES

ROBERSON ADDITION

WILCREST ADDITION

GENTRY 5TH ADDITION

RIDGE

CENTRAL

Project Baseline

+700 +800 +900 5+000 10+000

SEE SHEETS 62 FOR INTERSECTION TRAFFIC CONTROL INFORMATION.

SRB

SCALE

10 0 10 20

PLAN: Lat. & Long. (meters)

SIGNAL INTERCONNECTION PLAN
CENTRAL - STATION 9+700 TO STATION 10+000

SRB
924 NORTH MAIN
WICHITA, KANSAS 67203
316-264-9008
FAX 264-4621
http://www.feist.com/~srb
E-Mail: srb@feist.com

SAVOY, RUGGLES & BOHM, P.A.
ENGINEERING & SURVEYING

PROJECT NUMBER -

DRAWN	DESIGN	REVIEW	DATE	UTILITY	SRB JOB
J.R.A.	T.C.R.		Dec. 13, 2000		1218T

REVISED

DGN FILE: Interconnect 3

67

118