



NOTE: Bus Shelter to be Moved to a Location of the Artist's Choosing to be Modified and Restored Prior to Resetting in Proposed Location

*NOTE: Construct 4" Wide Variable Height Curb to Match Existing Parking Lot Grades while Maintaining Proper Sidewalk Grades for the Intersection (See Intersection Details). Costs to be Paid for Under Bid Item Concrete Sidewalk, 4"

NOTE: All paving bricks removed from the existing pavement shall be saved, cleaned, stockpiled re-used for final surface work in sidewalk areas as shown in plans. Should additional paving bricks be required, they will be available from the City of Wichita stockpiles. All costs associated with cleaning, stockpiling and hauling brick pavers shall be INCIDENTAL to the "Pavement &/or Curb & Gutter Removed".

NOTE: Paving Elevations are Based on 13.00 (Nav 88)

NOTE: Trees to be removed are marked as such:

Drawing File: E:\Projects\9th Street Corridor_16-02-E407\Civil 3D\Basemap
 Design: LP
 Drawn: LP
 Approved: T Alieri
 Scale: NOTED

Project No. 16-02-E407 CAPITAL IMPROVEMENT PROJECT
9TH STREET PAVING PLANS
 Sta. 18+00.00 to Sta. 23+50.00
9TH STREET 01315 to HILLSIDE

Baughman Company, P.A.
 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149
 ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE