



Construct Concrete Sidewalk 4" (5' Wide)

Construct Concrete Driveway (8" Reinforced) (30' Wide)

Construct Mono Edge Curb (4" High) (Var. 0' to 1' High)*

Construct Conc. Pmnt. 9" (NRD.J) on Crushed Rock Base 6", Reinf. (See Joint Plan)

Construct Conc. Pmnt. 9", Reinf. on Crushed Rock Base 6", Reinf. (See Intersection Details)

Construct Conc. Bench Pad with Bike Racks (See Bench Pad Details)

Construct Concrete Driveway (8" Reinforced) (30' Wide)

Construct Concrete Sidewalk 4" (5' Wide)

Construct Concrete Driveway (8" Reinforced) (26' Wide)

NOTE: Taper Proposed 5' Wide Sidewalk to Match Existing 4' Wide Sidewalk at the Project Limits

*NOTE: Construct 4" Wide Variable Height Curb to Match Existing Parking Lot Grades while Maintaining Proper Sidewalk Grades for the Intersection (See Intersection Details). Costs to be Paid for Under Bid Item Concrete Sidewalk, 4"

NOTE: Paving Elevations are Based on 13... (Nav 88)

NOTE: Trees to be removed are marked as such:

Drawing File: E:\Projects\9th Street Corridor_16-02-E407\Civil 3D\Basemap
 Project No. 16-02-E407 CAPITAL IMPROVEMENT PROJECT
 Design: LP
 Drawn: LP
 Approved: T Aliche
 Scale: NOTED

GROVE STREET PAVING PLANS
 Sta. 8+06.58 to Sta. 12+29.53
 9TH STREET (HILLSIDE)

Baughman Company, P.A.
 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149
 ENGINEERING | SURVEYING | PLANNING | LANDSCAPE ARCHITECTURE