

**BENCHMARK:**  
 BM #1 - Chiseled "X" on the Northwest Corner of the Inlet in the Northwest Corner of 29th Street North and Hoover Road.  
 B.L. Sta. 10+83.86, 23.34' Lt.  
 Elev. = 1331.59 (NAVD 88)

Remove Ex. Trees Between B.L. Sta. 11+90 to Sta. 14+90 within 50' East of the Section Line. All Cost Associated with this Work Shall be Considered **SUBSIDIARY** to the Measured Quantity Bid Items "Tree Removed, Large" or "Tree Removed, Small".

\* Cox Communications will relocate the Overhead Cable TV Lines off the Power Pole at B.L. Sta. 13+32, 41' Rt. prior to construction. The Contractor shall remove the pole and guy during construction if not already removed.

