

STA. 12+75.00, 70.5' LT.  
INSTALL 24 L.F. OF 30" RCP  
@ 0.29% W/PLUG  
IN=197.95  
OUT=197.88

STA 12+78.5, LINE 2  
CONST. STD. C.O.W. TYPE 1-A CURB INLET  
STACK ON TOP OF 7'x3' RCB (PRECAST)  
W=4'-4", L=11'-4"  
INLET TOP=204.46  
42.5 FT. LT. (∅ TO FRONT EXT. WALL)  
IN=197.88 (30" RCP-N.)  
IN & OUT=197.59 (7'x3' RCB-E. & W.)  
SEE SPECIAL DETAILS SHEET 60.

CONST. 6' CONC.  
SIDEWALK (4") (AE)


STA. 16+11.36, 59' LT.  
INSTALL 6 L.F. OF 30" RCP  
@ 0.31% W/PLUG  
IN=197.59  
OUT=197.54

STA 16+08.5, LINE 2  
CONST. STD. C.O.W. TYPE 1-A CURB INLET  
STACK ON TOP OF 9'x3' RCB (PRECAST)  
W=5'-4", L=11'-4"  
INLET TOP=203.24  
36.5 FT. LT. (∅ TO FRONT EXT. WALL)  
IN=197.54 (30" RCP-N.)  
IN=198.50 (15" RCP-S.)  
IN=197.25 (7'x3' RCB-W.)  
OUT=197.25 (9'x3' RCB-E.)  
SEE SPECIAL DETAILS SHEET 60.

CONST. COMB. CURB &  
GUTTER KNOT TYPE 1  
STA. 12+00 TO  
STA. 17+00

REMOVE EXIST. 5"  
A.C. PAVEMENT

STA. 16+08.5, LINE 2-A  
CONST. STD. C.O.W. TYPE 1-A CURB INLET  
W=4'-4", L=11'-4"  
INLET TOP=203.58  
25.5 FT. RT. (∅ TO FRONT EXT. WALL)  
OUT=198.79 (15" RCP-N.)

LEGEND  

 PAVEMENT, DRIVEWAY AND/OR  
SIDEWALK REMOVAL.

REVISED 11/01/93

KANSAS DEPARTMENT OF TRANSPORTATION

**21ST. STREET NORTH  
12+00 TO 17+00**

PROJECT NO. 87-U-1362-01 SEDGWICK CO.

**MID-KANSAS ENGINEERING CONSULTANTS, INC.**  
WICHITA, KANSAS

DESIGNED BY:	GJA	CHECKED BY:	DLH & KJS
DRAWN BY:	WNJ	DATE:	SHEET 33 OF 149