STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0673-01	2017	15	99

CONDUIT AND CABLE ROUTING TABLE

CONDUIT (FT)

CABLE (FT)

FROM	TO	CTR TO CTR DISTANCE (FT)	TRENCHED 1 1 IN RED	TRENCHED 1 1 IN GREEN	TRENCHED 2 2 IN RED	TRENCHED 2 2 IN GREEN	TRENCHED 3 3 IN RED	TRENCHED 3 3 IN GREEN	TRENCHED 4 4 IN RED	TRENCHED 4 4 IN GREEN	TRENCHED S SPARE 2 IN BLACK	BORED 6 2 IN RED	BORED 6 2 IN GREEN	BORED 7 3 IN RED	BORED 7 3 IN GREEN	ON STRUCTURE 8 2 IN RMC	POWER 1 3-#X/0	POWER 2 3-#4	POWER 3 3-#6	POWER 4 2-#X	POWER 5 2-#X	COMM. FIBER OPTIC (12) 12 SMFO	COMM. FIBER OPTIC (96) 96 SMFO	COMM. # CAT 6 CABLE	COMM. #	DEVICE 1 CCTV	DEVICE 2 DMS	DEVICE 3 VDS	DEVICE 4
K015SBC-04-069.0	SW PB (Exist.)	23																								66		198	
SW PB (Exist.)	NW PB (Exist.)	90																								96		288	
NW PB (Exist.)	SG Cabinet (Exist.)	12																								26		156	
SE TS Pole (Exist.)	SE PB (Exist.)	7																										50	
SE PB (Exist.)	NE PB (Exist.)	115																										121	
NE PB (Exist.)	NW PB (Exist.)	120																										378	
NE TS Pole (Exist.)	NE PB (Exist.)	29																										144	
TOTAL																										188		1335	

DATE	BY	
	REFERENCES NOTED	
	REFERENCES CHECKED	

Drawn By : examples
Plotted : 11/14/2017
File : c:\transystems\pw_local\transyscorp-pw1\ccbankal\d0521528\C-CCRT-M01-104.dgn

KANSAS DEPARTMENT OF TRANSPORTATION
SITE 4
K-15 & MEADOWLARK RD.
CABLE, CONDUIT & DEVICE TABLE

CADconform Certify This File

CADconform Certify This File