STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0673-01	2017	23	99

CONDUIT AND CABLE ROUTING TABLE

CONDUIT (FT)

CABLE (FT)

FROM	TO	CTR TO CTR DISTANCE (FT)	TRENCHED 1 1 IN RED	TRENCHED 1 1 IN GREEN	TRENCHED 2 2 IN RED	TRENCHED 2 2 IN GREEN	TRENCHED 3 3 IN RED	TRENCHED 3 3 IN GREEN	TRENCHED 4 4 IN RED	TRENCHED 4 4 IN GREEN	TRENCHED S SPARE 2 IN BLACK	BORED 6 2 IN RED	BORED 6 2 IN GREEN	BORED 7 3 IN RED	BORED 7 3 IN GREEN	ON STRUCTURE 8 2 IN RMC	POWER 1 3-#X/0	POWER 2 3-#4	POWER 3 3-#6	POWER 4 2-#X	POWER 5 2-#X	COMM. FIBER OPTIC (12) 12 SMFO	COMM. FIBER OPTIC (96) 96 SMFO	COMM. # CAT 6 CABLE	COMM. #	DEVICE 1 CCTV	DEVICE 2 DMS	DEVICE 3 VDS	DEVICE 4
K015SBC-08-073.1	PB (Exist.)	13																								56			
PB (Exist.)	SG Cabinet (Exist.)	13																				**				27			
PB (Exist.)	SV015-01	203											203									**							
SV015-01	PB015-01 (Exist.)	12				24																							
TOTAL						24							203									**				83			

** PRETERMINATED FIBER CONNECTOR INCLUDES MANUFACTURER SUPPLIED 12 SMFO PIGTAIL WITH ENOUGH LENGTH TO CONNECT TO SPLICE VAULT. THE UNIT COST FOR 12 SMFO SHALL BE SUBSIDIARY TO THE PRETERMINATED FIBER CONNECTOR. CONTRACTOR SHALL FIELD VERIFY LENGTH PRIOR TO ORDERING PRETERMINATED FIBER CONNECTOR WITH PIGTAIL.

DATE	BY	
	REFERENCES NOTED	
	REFERENCES CHECKED	

Drawn By : examples
Plotted : 11/14/2017
File : c:\transystems\pw_local\transyscorp-pw1\ccbankal\d0521528\IC-CCRT-M01-108.dgn

KANSAS DEPARTMENT OF TRANSPORTATION
SITE 8
K-15 & MACARTHUR RD.
CABLE, CONDUIT & DEVICE TABLE

CADconform Certify This File

CADconform Certify This File