STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0673-01	2017	27	99

CONDUIT AND CABLE ROUTING TABLE

CONDUIT (FT)

CABLE (FT)

FROM	TO	CTR TO CTR DISTANCE (FT)	TRENCHED 1 — 1 IN RED	TRENCHED 1 — 1 IN GREEN	TRENCHED 2 — 2 IN RED	TRENCHED 2 — 2 IN GREEN	TRENCHED 3 — 3 IN RED	TRENCHED 3 — 3 IN GREEN	TRENCHED 4 — 4 IN RED	TRENCHED 4 — 4 IN GREEN	TRENCHED S — SPARE 2 IN BLACK	BORED 6 — 2 IN RED	BORED 6 — 2 IN GREEN	BORED 7 — 3 IN RED	BORED 7 — 3 IN GREEN	ON STRUCTURE 8 — 2 IN RMC	POWER 1 — 3-#X/0	POWER 2 — 3-#4	POWER 3 — 3-#6	POWER 4 — 2-#X	POWER 5 — 2-#X	COMM. FIBER OPTIC (12) — 12 SMFO	COMM. FIBER OPTIC (96) — 96 SMFO	COMM. # — CAT 6 CABLE	COMM. #	DEVICE 1 — CCTV *	DEVICE 2 — DMS	DEVICE 3 — VDS	DEVICE 4
KSEBNBC-10-000.3	PB (Exist.)	11																								54			
PB (Exist.)	PB (Exist.)	81																								87			
PB (Exist.)	SG Cabinet (Exist.)	12																								26			
TOTAL																										167			

* CONTRACTOR SHALL TEST EXISTING ETHERNET WIRE (FROM RADIO) FOR DAMAGE & CONNECTIVITY. IF WIRE IS IN SATISFACTORY CONDITION, CONTRACTOR MAY REUSE WIRE FOR CCTV CABLE.

DATE	BY	
	REFERENCES NOTED	
	REFERENCES CHECKED	

Drawn By : examples
Plotted : 11/14/2017
File : c:\transystems\pw_local\transyscorp-pw1\ccbanka\d0521528\C-CCRT-M01-110.dgn

KANSAS DEPARTMENT OF TRANSPORTATION
SITE 10
SOUTHEAST BLVD. & WASSALL ST.
CABLE, CONDUIT & DEVICE TABLE

CADconform Certify This File
CADconform Certify This File