STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0673-01	2017	29	99

CONDUIT AND CABLE ROUTING TABLE

FROM	TO	CTR TO CTR DISTANCE (FT)	CONDUIT (FT)														CABLE (FT)												
			TRENCHED									BORED				ON STRUCTURE	POWER					COMM.		COMM.		DEVICE			
			1		2		3		4		S	6		7		8	1	2	3	4	5	FIBER OPTIC		#		1	2	3	4
			1 IN		2 IN		3 IN		4 IN		SPARE 2 IN	2 IN		3 IN		2 IN RMC	3-#X/0	3-#4	3-#6	2-#X	2-#X	12 / 12 SMFO	96 / 96 SMFO	CAT 6 CABLE		CCTV *	DMS	VDS	
			RED	GREEN	RED	GREEN	RED	GREEN	RED	GREEN	BLACK	RED	GREEN	RED	GREEN														
KSEBSBC-11-001.1	PB (Exist.)	28																								71			
PB (Exist.)	SG Cabinet (Exist.)	8																								22			
TOTAL																										93			

* CONTRACTOR SHALL TEST EXISTING ETHERNET WIRE (FROM RADIO) FOR DAMAGE & CONNECTIVITY. IF WIRE IS IN SATISFACTORY CONDITION, CONTRACTOR MAY REUSE WIRE FOR CCTV CABLE.

DATE	BY	
	REFERENCES NOTED	
	REFERENCES CHECKED	

Drawn By : examples Plotted : 11/14/2017
File : c:\transystems\pw_local\transyscorp-pw1\ccbanka\d0521528\G-CCRT-M01-111.dgn

KANSAS DEPARTMENT OF TRANSPORTATION
SITE II
SOUTHEAST BLVD. & HYDRAULIC ST.
CABLE, CONDUIT & DEVICE TABLE

CADconform Certify This File
CADconform Certify This File