STATE	PROJECT NO.	YEAR	SHEET NO.	TOTAL SHEETS
KANSAS	87 N-0673-01	2017	41	99

CONDUIT AND CABLE ROUTING TABLE

CONDUIT (FT)

FROM	TO	CTR TO CTR DISTANCE (FT)	TRENCHED 1 1 IN RED	TRENCHED 1 1 IN GREEN	TRENCHED 2 2 IN RED	TRENCHED 2 2 IN GREEN	TRENCHED 3 3 IN RED	TRENCHED 3 3 IN GREEN	TRENCHED 4 4 IN RED	TRENCHED 4 4 IN GREEN	TRENCHED S SPARE 2 IN BLACK	BORED 6 2 IN RED	BORED 6 2 IN GREEN	BORED 7 3 IN RED	BORED 7 3 IN GREEN	ON STRUCTURE 8 2 IN RMC
KWASHNBC-17-003.0	PB (Exist.)	8														
PB (Exist.)	SG Cabinet (Exist.)	58														
TOTAL																

CABLE (FT)

FROM	TO	POWER 1 3-#X/0	POWER 2 3-#4	POWER 3 3-#6	POWER 4 2-#X	POWER 5 2-#X	COMM. FIBER OPTIC 12 12 SMFO	COMM. FIBER OPTIC 96 96 SMFO	COMM. # CAT 6 CABLE	COMM. #	DEVICE 1 CCTV *	DEVICE 2 DMS	DEVICE 3 VDS	DEVICE 4
KWASHNBC-17-003.0	PB (Exist.)										51			
PB (Exist.)	SG Cabinet (Exist.)										72			
TOTAL											123			

* CONTRACTOR SHALL TEST EXISTING ETHERNET WIRE (FROM RADIO) FOR DAMAGE & CONNECTIVITY. IF WIRE IS IN SATISFACTORY CONDITION, CONTRACTOR MAY REUSE WIRE FOR CCTV CABLE.

DATE	BY	
	REFERENCES NOTED	
	REFERENCES CHECKED	

Drawn By : examples Plotted : 11/14/2017
File : c:\transystems\pw_local\transyscorp-pw1\ccbanka\d0521528\G-CCRT-M01-117.dgn

KANSAS DEPARTMENT OF TRANSPORTATION
SITE 17
WASHINGTON AVE. & DEWEY ST.
CABLE, CONDUIT & DEVICE TABLE

CADconform Certify This File

CADconform Certify This File