

Bellick St.

Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
0+00.00	116.47	0.00	0.00	0.00	0.00	0.00	0.00
0+50.00	99.09	0.00	199.60	0.00	199.60	0.00	199.60
1+00.00	80.69	0.00	166.46	0.00	366.06	0.00	366.06
1+50.00	95.47	0.00	163.11	0.00	529.17	0.00	529.17
2+00.00	26.76	15.77	113.18	14.60	642.35	14.60	627.75
2+50.00	2.56	41.38	27.15	52.91	669.50	67.51	601.99
3+00.00	0.00	87.70	2.37	119.52	671.87	187.03	484.84
3+50.00	0.00	104.39	0.00	177.86	671.87	364.89	306.98
4+00.00	0.00	84.88	0.00	175.25	671.87	540.14	131.73
4+50.00	3.82	47.28	3.54	122.37	675.40	662.51	12.89
4+79.48	28.93	13.65	17.87	33.26	693.28	695.77	-2.49
5+00.00	37.29	13.92	25.16	10.48	718.44	706.25	12.20
5+20.38	49.74	5.69	32.85	7.40	751.30	713.65	37.65
5+25.00	53.10	5.17	8.79	0.93	760.09	714.58	45.51
5+50.00	56.11	4.13	50.56	4.31	810.65	718.89	91.76
5+61.29	52.19	3.95	22.65	1.69	833.29	720.58	112.72
6+00.00	41.25	5.13	66.98	6.51	900.27	727.08	173.19
6+50.00	46.69	0.35	81.42	5.07	981.69	732.15	249.54
6+79.47	0.00	0.00	25.48	0.19	1007.17	732.34	274.83
7+00.00	0.00	0.00	0.00	0.00	1007.17	732.34	274.83
7+16.11	0.00	0.00	0.00	0.00	1007.17	732.34	274.83

Marold St.

Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
0+00.00	133.21	0.00	0.00	0.00	0.00	0.00	0.00
0+50.00	140.36	0.00	253.31	0.00	253.31	0.00	253.31
1+00.00	131.23	0.00	251.47	0.00	504.78	0.00	504.78
1+11.95	120.08	0.00	55.60	0.00	560.39	0.00	560.39
1+48.95	0.00	0.00	82.27	0.00	642.66	0.00	642.66

Thoroughbred Ct.

Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
0+00.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
0+37.00	10.88	33.38	7.45	22.87	7.45	22.87	-15.42
0+50.00	15.64	28.80	6.39	14.97	13.84	37.84	-24.00
1+00.00	34.97	5.43	46.87	31.69	60.71	69.53	-8.83
1+50.00	68.60	0.00	95.90	5.03	156.61	74.56	82.05
2+00.00	109.99	0.00	165.36	0.00	321.97	74.56	247.41
2+50.00	108.98	0.00	202.75	0.00	524.72	74.56	450.16
3+00.00	104.41	0.07	197.58	0.06	722.30	74.62	647.68
3+20.46	106.30	0.10	79.82	0.06	802.12	74.68	727.44
3+47.99	129.28	0.04	120.11	0.07	922.23	74.75	847.47
3+54.07	130.29	0.03	29.24	0.01	951.46	74.76	876.70
3+76.24	151.59	0.01	115.75	0.02	1067.21	74.78	992.43


Thoroughbred St.

Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
-0+00.00	34.65	9.19	0.00	0.00	0.00	0.00	0.00
0+25.00	37.25	5.60	33.29	6.85	33.29	6.85	26.44
0+50.00	48.53	0.90	39.72	3.01	73.00	9.86	63.14
0+51.53	49.41	0.69	2.77	0.04	75.77	9.91	65.87
0+75.00	60.26	1.42	47.67	0.92	123.45	10.82	112.62
1+00.00	86.12	0.20	67.77	0.75	191.22	11.58	179.64
1+03.05	88.71	0.09	9.88	0.02	201.10	11.59	189.51
1+50.00	115.25	0.00	177.31	0.07	378.42	11.67	366.75
2+00.00	100.91	0.00	200.14	0.00	578.56	11.67	566.89
2+50.00	116.81	0.00	201.59	0.00	780.15	11.67	768.49
3+00.00	133.98	0.00	232.21	0.00	1012.36	11.67	1000.70
3+50.00	130.20	0.00	244.61	0.00	1256.97	11.67	1245.30
4+00.00	116.88	0.00	228.78	0.00	1485.75	11.67	1474.08
4+50.00	0.00	0.00	108.22	0.00	1593.97	11.67	1582.31
4+76.42	0.00	0.00	0.00	0.00	1593.97	11.67	1582.31

Bellick Ct.

Total Volume Table							
Station	Cut Area	Fill Area	Cut Vol	Fill Vol	Cum Cut Vol	Cum Fill Vol	Net Vol
0+37.50	0.00	204.61	0.00	0.00	0.00	0.00	0.00
0+50.00	0.00	218.19	0.00	97.87	0.00	97.87	-97.87
0+85.00	0.00	298.81	0.00	309.17	0.00	407.04	-407.04

Cheryl's Hollow 2nd Addition - Phase 2
Summary of Earthwork
 Wichita, Kansas

	PROJECT NUMBER 472-85405			SHEET 10.9
	KEM NO. 17104	FILE	DATE 11/2017	
DESIGN KM	DRAWN SS	REVISED		