

GENERAL NOTE:

On surfacing projects the 150 mm of Compaction Type AA, shown for the center portion on the roadbed, is for the purpose of restoring the original Compaction Type AA which may have been lost since grading operations. The exact locations of this Compaction Type AA which will be required, is to be determined by the Engineer at the time of construction. This work shall be paid under the bid item "Compaction of Earthwork (Type AA)(MR-)".

Over all structures, unless otherwise directed by the Engineer, where the top of the hubguard is level with or above the finished shoulder grade, the earth cover over the structure slab shall be removed and backfilled with _____ material as directed by the Engineer. The removal of this material will be subsidiary.

The _____ material used to backfill over the structure shall be paid for at the prices shown in the contract.

The earth shoulders shall be compacted full depth (Type B)(MR 90) except, when ordered by the Engineer, the top 75 mm shall be left uncompacted for seeding.

All side roads and house entrances shall be surfaced with _____ to the R/W line as indicated on the detail. All side roads and house entrances with existing asphalt surface shall be surfaced with _____ at least to the R/W line or to the end of construction, as directed by the Engineer. Each mailbox turnout (ON PROJECTS WHERE STABILIZED SHOULDERS ARE NOT SPECIFIED) shall be surfaced with _____ to the limits shown on the detail.

Surfacing material (SA- _____) shall be used for surfacing house entrances and side roads (_____ m³/m²) beyond the limits of the asphalt surface to the limits of construction as determined by the Engineer.

The thickness of side road and entrance surfacing may be increased to the same thickness as the stabilized shoulder within the approximate limits of the shoulder.

On projects which specify both bituminous base and surface course materials, side roads, house entrances and mailbox turnouts may be surfaced with both materials at the contractors option, with the approval of the Engineer.

Quantities for aggregate for shoulders, AS-1, are calculated on the basis of 2 400 kg/m³.


Quantities for stabilized base course, AB-3, are calculated on the basis of 2 500 kg/m³. Mass per m³ includes moisture allowed by specification.

The base course shall be constructed to the plan thickness as shown.

Thicknesses indicated for all construction which is paid for on a mass or volume basis are approximate and may vary to correct for unevenness in the foundations or for other normal unevenness encountered in placement operations.

A tack coat of _____ shall be provided between each lift of all base courses and surface courses and under the first lift of base or surface courses when they are placed on an existing bituminous, brick, or concrete surface, when so ordered by the Engineer and at the rate designated by him/her. Quantities are included for these tacks calculated at the rate of 0.14 L/m².

Bituminous Material quantities are calculated on the basis of 1000 kg/m³.



TYPICAL PROFILE AT GRADE CONTROL POINTS

The Contractor shall cut the subgrade in accordance with this profile at all grade control points, i.e.; existing pavements, grade bridges, R.R. crossings, and at changes in thickness of base or surface courses. The ratio of $\frac{L}{D}$ shall be not less than 300 mm per mm thickness.

The work of cutting the subgrade and disposing of excess excavated material shall be subsidiary to other items in the contract.


SUMMARY OF QUANTITIES

| ITEM | SIDE | BM-2 BASE | BM-2 SURFACE | ASPHALT FOR BASE | ASPHALT FOR SURFACE | UNIT |
|------------------------|------|-----------|--------------|------------------|---------------------|------|
| PAWNEE AVENUE | | | | | | |
| 1+289.075 TO 1+381.755 | LT. | 357.7 | 119.2 | 18.6 | 6.2 | t |
| 1+301.543 TO 1+381.775 | RT. | 319.3 | 106.4 | 16.6 | 5.5 | t |
| 1+425.605 TO 1+549.300 | LT. | 454.7 | 151.6 | 23.7 | 7.9 | t |
| 1+425.605 TO 1+528.657 | RT. | 405.0 | 135.0 | 21.1 | 7.0 | t |
| OLIVER STREET | | | | | | |
| 5+726.757 TO 5+831.330 | LT. | 407.5 | 135.8 | 21.2 | 7.1 | t |
| 5+726.757 TO 5+831.330 | RT. | 351.8 | 117.3 | 18.3 | 6.1 | t |
| 5+876.360 TO 5+993.272 | LT. | 427.2 | 142.4 | 22.3 | 7.4 | t |
| 5+876.360 TO 5+993.272 | RT. | 322.1 | 107.4 | 16.8 | 5.6 | t |

THESE QUANTITIES ARE FOR INFORMATION ONLY.

Note: For projects with stabilized shoulders, the face of the Mail Box to be in a vertical line with the top edge of the shoulder surfacing.


| FHWA REGION NO. | STATE | PROJECT NO. | YEAR | SHEET NO. | TOTAL SHEETS |
|-----------------|--------|--------------|------|-----------|--------------|
| 7 | KANSAS | 87 N-0092-01 | 1999 | 50 | 75 |




Width shall be 2.4 m or shoulder width, whichever is greater.

Note: The Face of Mail Box should be in a vertical line with the edge of the shoulder.

SECTION A-A



DETAIL FOR SURFACING OF MAIL BOX TURNOUTS



Entrance or side road is symmetrical about its center line.

FLARE OF SHOULDERS AT ENTRANCES AND SIDE ROADS

Dimensions for mound entrances or sideroads and those with drainage structures shall be similar with the exception of side slopes within the project clear zone. These slopes shall be as follows:

Normal Slope (but not steeper than 1:6 at approximate centerline of structure or appropriate clear zone width for entrances or sideroads containing drainage structures.

1:8 Slope at the appropriate clear zone shall apply to all mound entrances and mound side roads to 3 m fill height. Normal Slope (but not steeper than 1:6) over 3 m fill height.

RATES OF APPLICATION

| RATE | UNIT | ITEM |
|------|------|----------------------------|
| 5.5% | | BM-2 Base and BM-2 Surface |

† Computed at the rate of 5.5% by dry weight of aggregate.
 †† Computed at the rate of 2322 kg/m³ (total mix aggregate and asphalt)

RECAPITULATION OF QUANTITIES

| ITEM | TOTAL | UNIT |
|---|-------|-------|
| ASPHALTIC CONCRETE PAVEMENT (200 mm)(PG-70-28-) | 8743 | Sq. m |

| NO. | DATE | REVISIONS | BY | APP'D. |
|-----|----------|-----------------------------|--------|--------|
| 3 | | | | |
| 2 | 12-26-96 | Rev. units for tack rate | R.J.S. | J.O.B. |
| 1 | 2-26-96 | Type AA Compaction Bid Item | R.J.S. | J.O.B. |

**KANSAS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 (Sur facing)**

| DESIGNED | DETAILED | QUANTITIES | TRACED |
|------------|------------|-----------------------|------------------|
| RD940 SI | I-14-97 | APP'D James O. Brewer | B.N.B. |
| DESIGN CK. | DETAIL CK. | QUAN. CK. | TRACE CK. R.J.S. |