

JEWELL CT W CY Excavation (unadjusted)				JEWELL CT W CY Compacted Fill (unadjusted)				JEWELL CT W CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total	Station	Area	Volume	Total
0+38.49	8.79	0.0	0.0	0+38.49	15.95	0.0	0.0	0+38.49	13.94	0.0	0.0
0+50	8.65	3.7	3.7	0+50	16.21	6.9	6.9	0+50	12.76	5.7	5.7
1+00	21.71	28.1	31.8	1+00	0.00	15.0	21.9	1+00	6.57	17.9	23.6
1+50	21.93	40.4	72.2	1+50	0.00	0.0	21.9	1+50	4.91	10.6	34.2
2+00	24.33	42.8	115.1	2+00	0.00	0.0	21.9	2+00	3.79	8.1	42.3
2+50	21.69	42.6	157.7	2+50	0.00	0.0	21.9	2+50	4.08	7.3	49.6
3+00	31.22	49.0	206.7	3+00	0.00	0.0	21.9	3+00	0.91	4.6	54.2
3+32.10	70.95	60.7	267.4	3+32.10	0.00	0.0	21.9	3+32.10	1.02	1.1	55.3
3+57.09	60.81	61.0	328.4	3+57.09	0.00	0.0	21.9	3+57.09	0.92	0.9	56.2
3+72.09	61.29	33.9	362.3	3+72.09	0.00	0.0	21.9	3+72.09	0.49	0.4	56.6
3+92.09	33.52	35.1	397.4	3+92.09	0.00	0.0	21.9	3+92.09	0.42	0.3	57.0
4+07.09	0.00	9.3	406.7	4+07.09	0.00	0.0	21.9	4+07.09	0.00	0.1	57.1

