

TWINLAKE DRIVE

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
1+34.37	54.16	0.25	31.93	0.07	31.93	0.07
1+50	55.90	0.00	98.88	0.00	130.61	0.07
2+00	50.48	0.00	91.21	0.21	221.82	0.28
2+50	47.87	0.24	88.98	0.41	310.80	0.69
3+00	48.42	0.18	94.49	0.34	405.29	1.03
3+50	53.81	0.17	99.08	0.16	504.37	1.19
4+00	53.20	0.00	98.88	0.00	603.25	1.19
4+50	53.59	0.00	101.73	0.00	704.97	1.19
5+00	56.28	0.00	99.94	0.12	804.91	1.31
5+50	51.66	0.13	93.38	0.12	898.29	1.43
6+00	49.19	0.00	99.96	0.20	998.25	1.63
6+50	58.76	0.22	109.26	0.20	1107.51	1.83
7+00	59.24	0.00	103.07	0.00	1210.58	1.84
7+50	52.08	0.00	83.36	2.07	1293.94	3.90
8+00	37.95	2.23	61.38	10.72	1355.33	14.62
8+50	28.34	9.34	50.22	19.14	1405.55	33.77
9+00	25.89	11.33	57.19	9.49	1462.73	43.26
9+44.12	44.10	0.28	27.63	0.09	1490.36	43.34
9+59.78	50.50	0.05	52.78	0.17	1543.14	43.52
9+90.33	41.70	0.32	45.85	1.13	1588.99	44.65
10+20.88	38.09	2.02	21.42	2.32	1610.40	46.96
10+37.17	32.18	6.25	14.77	3.35	1625.17	50.31
10+50	29.99	7.83	47.79	20.97	1672.96	71.28
11+00	21.62	14.82	56.25	16.79	1729.21	88.07
11+50	39.11	3.32	76.17	3.64	1805.38	91.71
12+00	43.15	0.62	70.42	5.82	1875.80	97.54
12+50	32.90	5.67	46.41	7.37	1922.21	104.91
12+86.20	36.33	5.32	0.00	0.00	1922.21	104.91

WATSON

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
1+34.07	41.73	1.17	28.52	0.34	28.52	0.34
1+50	54.95	0.00	108.52	0.00	137.04	0.34
2+00	62.26	0.00	111.24	0.00	248.28	0.34
2+50	57.89	0.00	113.07	0.00	361.34	0.35
3+00	64.23	0.00	119.96	0.00	481.30	0.35
3+50	65.32	0.00	96.51	2.28	577.81	2.63
4+00	38.91	2.46	59.21	13.42	637.02	16.05
4+50	25.03	12.03	56.08	14.51	693.10	30.56
5+00	35.53	3.64	69.64	7.02	762.74	37.58
5+50	39.68	3.95	72.74	8.47	835.48	46.05
6+00	38.88	5.20	72.88	7.28	908.36	53.32
6+50	39.97	2.55	76.66	4.24	985.02	57.57
7+00	42.99	1.98	80.18	4.51	1065.20	62.08
7+50	43.83	2.76	83.61	3.38	1148.81	65.46
8+00	46.62	0.85	80.20	2.11	1229.01	67.58
8+50	40.02	1.45	65.30	8.38	1294.32	75.95
9+00	30.51	7.60	7.46	1.93	1301.77	77.88
9+06.66	29.97	8.03	18.35	3.42	1320.13	81.30
9+23.09	29.91	4.03	17.13	1.77	1337.25	83.07
9+38.02	31.22	3.40	0.00	0.00	1337.25	83.07

CREEKSIDE LN.

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
8+35.49	26.21	8.37	13.19	5.37	13.19	5.37
8+50	22.86	11.61	31.89	31.19	45.08	36.56
9+00	11.58	22.08	28.44	37.54	73.51	74.10
9+50	19.14	18.46	8.63	9.37	82.15	83.47
9+63	16.72	20.47	16.93	7.47	99.07	90.94
9+82.50	30.15	0.21	22.97	0.09	122.05	91.03
10+00	40.74	0.07	28.97	0.02	151.01	91.05
10+17.50	48.64	0.01	27.09	3.02	178.10	94.07
10+37	26.38	8.35	15.71	2.64	193.81	96.71
10+50	38.87	2.63	72.86	2.69	266.67	99.40
11+00	39.81	0.27	64.34	4.92	331.01	104.33
11+50	29.67	5.04	51.58	12.56	382.59	116.89
12+00	26.04	8.52	43.22	21.00	425.81	137.89
12+50	20.65	14.16	13.42	7.13	439.23	145.01
12+65.92	24.88	10.02	27.93	6.31	467.16	151.33
12+85.42	52.45	7.47	24.26	6.82	491.43	158.15
13+02.93	22.38	13.57	13.71	9.12	505.14	167.27
13+20.43	19.93	14.59	13.48	11.12	518.62	178.39
13+39.93	17.41	16.21	7.46	5.43	526.08	183.82
13+50	22.59	12.89	47.95	18.77	574.03	202.59
14+00	29.20	7.38	58.12	8.89	632.15	211.48
14+50	33.57	2.22	62.16	5.60	694.31	217.08
15+00	33.57	3.82	11.22	2.28	705.53	219.36
15+10.41	24.61	8.00	0.00	0.00	705.53	219.36


TWINLAKE CT

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+30.67	1.34	113.78	3.69	61.19	3.69	61.19
0+50	8.95	57.15	6.78	143.63	10.46	204.82
0+90.89	0.00	132.53	3.02	26.75	13.49	231.56
1+00	17.93	26.02	8.93	35.90	22.42	267.46
1+26.89	0.00	46.07	0.00	12.37	22.42	279.83
1+41.39	0.00	0.00	0.00	0.00	22.42	279.83

LAGUNA (SOUTH)

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+33.86	9.38	25.02	4.80	15.88	4.80	15.88
0+50	6.67	28.09	7.28	63.63	12.08	79.51
1+00	1.19	40.63	1.10	91.73	13.18	171.24
1+50	0.00	58.43	0.00	26.11	13.18	197.34
1+61.61	0.00	63.01	0.00	0.00	13.18	197.34

Clear Creek Addition, Paving Improvements
Earthwork Tables
WICHITA, KANSAS



Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main
Wichita, Kansas 67203
www.rbkansas.com
(316) 264-8008
(316) 264-4621 fax
E-mail: info@rbkansas.com

DRAWING FILE: EARTHWORK TABLES
PROJECT NUMBER: 472-83743

DESIGN: KWL
DRAWN: TEB
REVIEW:
UTILITY:
DATE: June 25, 2003
SHEET: 39 OF 40