

GENERAL NOTES

THE EROSION CONTROL DEVICES SHOWN ON THIS SHEET ARE CONSIDERED MINIMUM STANDARDS. WHENEVER SEDIMENT ENTERS THE STREETS, STORM SEWERS, DITCHES, OR PONDS, CONTRACTOR WILL INSTALL ADDITIONAL DEVICES, AS NEEDED, TO CORRECT THE PROBLEM.

THE EROSION CONTROL DEVICES SHOWN HEREON MUST BE IN PLACE AT ALL TIMES DURING CONSTRUCTION UNTIL SUCH TIME AS THE SITE IS REESTABLISHED WITH PAVING OR GRASS. TEMPORARY OR PERMANENT SEEDING AND MULCH WILL BE INSTALLED WHEN EARTHWORK ACTIVITIES CEASE IN AN AREA FOR 14 DAYS OR MORE.

BACK OF CURB PROTECTION: AS SHOWN ON CITY STANDARD DETAILS. THESE DEVICES MUST REMAIN IN PLACE UNTIL THE AREA BETWEEN THE CURB AND RIGHT-OF-WAY LINE HAS BEEN PERMANENTLY STABILIZED.

SCALE: 1"=50'

Silt Fence Barrier
See Detail Sheet No. 29.

S.E. Corner of Lot 4,
Block 2, Oak Creek Addition

PROPOSED PAVING IMPROVEMENTS

OAK CREEK 3RD

Back of Curb Protection
See Detail Sheet No. 28.

Curb Inlet Protection (Typ. of 4)
See Detail Sheet No. 31.

Area Inlet Protection (Typ. of 1)
See Detail Sheet Nos. 29 & 30.


FUTURE PAVING IMPROVEMENTS

SPARE EXISTING TREES

LEGEND

- x— Silt Fence Barrier
- ⊙ Area Inlet Protection
- Curb Inlet Protection

NOTE:
CONTRACTOR SHALL NOT REMOVE ANY TREES FROM THE PROJECT SITE WITHOUT SPECIFIC APPROVAL OF THE OWNER AND/OR ENGINEER.



No.	Revision	By	Date
OAK CREEK 3RD			
EROSION CONTROL PLAN			
Professional Engineering Consultants, P.A.			
303 S. TOPEKA • WICHITA, KANSAS 67202			
316-262-2691 • FAX 316-262-3003			
Designed by	BDB, BMM	Job No.	35-06572-000
Drawn by	BJS, TAT	Date	February 2006
			Sheet 27 of 45