

KINKAID / STONEYBROOK

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
1+00	79.43	0.00	29.42	0.00	29.42	0.00
1+20	0.00	0.00			40.73	10.17
1+50	20.36	18.30	47.29	24.21	88.02	34.38
2+00	30.71	7.85	55.49	15.70	143.51	50.08
2+50	29.22	9.10	50.78	18.93	194.30	69.00
3+00	25.62	11.34	39.95	27.86	234.25	96.86
3+50	17.53	18.75	22.63	45.63	256.88	142.49
4+00	6.91	30.53	9.22	63.81	266.09	206.31
4+50	3.04	38.39	4.28	33.54	270.37	239.85
4+75.97	5.85	31.36	6.50	24.99	276.87	264.84
5+00	8.08	28.38	14.71	54.00	291.57	318.84
5+50	7.25	33.75	20.04	50.02	311.61	368.86
6+00	13.92	22.52	22.69	22.56	334.30	391.42
6+32.75	23.56	13.85	16.82	7.35	351.12	398.78
6+50	29.10	9.18	74.03	9.18	425.16	407.96
7+00	50.85	0.73	47.09	0.68	472.24	408.64

STONEYBROOK

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
1+00	12.04	25.28	36.72	33.25	36.72	33.25
1+50	27.62	10.64			95.74	48.05
2+00	36.12	5.34	22.71	5.58	118.45	53.63
2+18.88	28.82	10.60	31.26	13.84	149.71	67.47
2+50	25.68	12.37	73.79	11.45	223.50	78.92
3+00	54.01	0.00	101.72	0.00	325.22	78.92
3+50	55.85	0.00	48.22	0.20	373.43	79.12
3+75.96	44.44	0.41	38.50	0.85	411.93	79.97
4+00	42.03	1.50	83.95	1.60	495.88	81.57
4+50	48.64	0.23	73.55	0.41	569.43	81.98
4+89.96	50.74	0.32	19.72	0.07	589.15	82.05
5+00	53.70	0.24	105.70	0.36	694.85	82.41
5+50	57.80	0.32	99.72	0.93	794.57	83.34
6+00	47.32	1.13	61.20	12.34	855.77	95.67
6+47.04	22.23	15.69	2.43	1.73	858.20	97.40
6+50	22.08	15.81	36.97	32.43	895.17	129.83
7+00	17.85	19.21	21.62	46.70	916.79	176.53
7+50	5.50	31.23	8.25	64.36	925.03	240.89
8+00	3.41	38.28	2.84	31.28	927.87	272.17
8+21.21	3.82	41.37	2.03	22.05	929.91	294.23

KINKAID CIRCLE

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+00	0.00	0.00	22.44	4.00	22.44	4.00
0+34.66	34.97	6.23	17.82	3.40	40.26	7.40
0+50	26.52	9.60	34.57	22.95	74.84	30.35
0+94.25	15.02	23.47	11.11	46.56	85.95	76.91
1+31.43	1.11	44.15	0.51	57.89	86.45	134.80
1+56.07	0.00	82.71	0.00	106.53	86.45	241.33
1+81.42	0.00	144.22	0.00	147.00	86.45	388.34
2+16.92	0.00	79.39	0.01	22.52	86.46	410.85
2+31.40	0.02	4.58	0.00	0.00	86.46	410.86


STONEYBROOK CT. (WEST)

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+32.71	32.94	2.64	20.49	2.12	20.49	2.12
0+50	31.06	3.98	8.25	1.16	28.74	3.28
0+57.26	30.31	4.63	100.18	26.64	128.92	29.92
1+37.50	36.85	13.86	38.56	14.20	167.48	44.12
1+62.94	45.00	16.28	22.81	9.71	190.29	53.83
1+77.94	37.12	18.66	14.09	16.33	204.38	70.15
1+98.44	0.00	24.35	0.00	7.68	204.38	77.84

STONEYBROOK CT. (EAST)

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+32.71	25.59	9.58	9.11	4.53	9.11	4.53
0+43.17	21.42	13.82	38.60	44.85	47.71	49.38
1+06	11.68	25.04	15.48	27.04	63.19	76.43
1+35.04	17.11	25.25	19.60	24.22	82.79	100.65
1+60.40	24.61	26.33	10.49	16.17	93.27	116.82
1+75.40	13.14	31.87	4.99	23.07	98.26	139.89
1+95.90	0.00	28.90	0.00	0.00	98.26	139.89

BRENTWOOD SOUTH ADDITION
EARTHWORK TABLES
WICHITA, KANSAS



Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main
Wichita, Kansas 67203
www.rbkansas.com
(316) 264-8008
(316) 264-4621 fax
E-mail: info@rbkansas.com

DESIGN KWL
DRAWN RA
REVIEW
UTILITY

REVISION
2003
SHEET
35
OF

DRAWING FILE
XS

PROJECT NUMBER
472-83445

DATE
June 23, 2003

36