

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
18+69.78	89.61	0.00				
19+00	55.56	0.36	81.24	0.20	81.24	0.20
19+50	53.99	0.21	101.43	0.53	182.67	0.73
20+00	71.52	0.00	116.21	0.20	298.89	0.93
20+50	63.04	0.00	124.59	0.00	423.47	0.93
21+00	45.58	3.13	100.57	2.89	524.04	3.82
21+50	61.35	0.00	99.01	2.89	623.05	6.72
22+00	75.04	0.00	126.29	0.00	749.34	6.72
22+50	43.98	4.87	110.21	4.51	859.55	11.22
23+00	50.76	0.93	87.72	5.37	947.27	16.60
23+50	44.80	3.61	88.48	4.20	1035.75	20.80
24+00	76.26	0.00	112.09	3.34	1147.84	24.14
24+50	71.55	0.00	136.86	0.00	1284.70	24.14
24+57.07	68.95	0.00	18.39	0.00	1303.10	24.14
24+76.57	84.34	0.00	55.35	0.00	1358.45	24.14
24+94.07	74.57	0.00	51.50	0.00	1409.95	24.14
25+11.57	73.91	0.03	48.12	0.01	1458.07	24.15
25+31.07	45.27	2.34	43.04	0.85	1501.11	25.00
25+50	41.36	5.12	30.37	2.62	1531.48	27.62
26+00	31.77	8.92	67.71	13.00	1599.19	40.62
26+50	24.77	15.52	52.35	22.63	1651.53	63.25
27+00	36.52	9.34	56.75	23.01	1708.28	86.26
27+50	54.36	0.24	84.14	8.87	1792.42	95.13
27+61.07	60.20	0.00	23.48	0.05	1815.91	95.18
27+80.57	95.53	0.00	56.23	0.00	1872.14	95.18
27+98.07	91.31	0.00	60.55	0.00	1932.69	95.18
28+15.57	88.01	0.67	58.11	0.22	1990.80	95.40
28+35.07	54.36	0.24	51.41	0.33	2042.22	95.73
28+50	53.32	1.20	29.77	0.40	2071.98	96.13
29+00	72.17	0.00	116.19	1.11	2188.18	97.24
29+50	0.00	0.00	66.82	0.00	2255.00	97.24
			0.00	0.00	2255.00	97.24


STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+37	29.67	16.93				
0+50	27.13	19.31	13.67	8.72	13.67	8.72
1+00	17.32	28.83	41.16	44.58	54.83	53.30
1+50	7.76	39.15	23.22	62.95	78.05	116.25
2+00	0.00	86.30	7.18	116.16	85.24	232.41
2+01.65	0.28	74.36	0.01	4.91	85.25	237.32
2+25.42	0.00	122.62	0.12	86.71	85.37	324.02
2+60.42	0.00	148.79	0.00	175.92	85.37	499.94
2+75.42	0.00	0.00	0.00	41.33	85.37	541.27
			0.00	0.00	85.37	541.27

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+37	85.80	0.00				
0+50	90.86	0.00	42.53	0.00	42.53	0.00
0+75.32	100.84	0.00	89.87	0.00	132.40	0.00
1+00	91.98	0.00	87.88	0.00	220.28	0.00
1+50	79.25	0.00	157.17	0.00	377.45	0.00
1+53.06	78.59	0.00	8.85	0.00	386.29	0.00
2+00	78.29	0.00	136.36	0.00	522.66	0.00
2+50	95.75	0.00	161.15	0.00	683.80	0.00
2+70	98.66	0.00	72.00	0.00	755.81	0.00
3+00	92.51	0.00	106.21	0.00	862.01	0.00
3+50	75.22	0.00	155.31	0.00	1017.32	0.00
4+00	58.31	0.00	123.64	0.00	1140.97	0.00
4+50	44.93	3.55	95.59	3.29	1236.55	3.29
5+00	56.29	0.30	93.72	3.57	1330.28	6.86
5+50	74.53	0.00	121.13	0.28	1451.41	7.14
6+00	57.64	0.01	122.37	0.01	1573.78	7.15
6+50	44.52	3.84	94.59	3.57	1668.37	10.72
6+98.68	44.52	3.84	80.26	6.93	1748.63	17.65
			0.00	0.00	1748.63	17.65

STATION	AREAS		VOLUMES		CUMULATIVE VOLUMES	
	Square Feet		Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+37	39.29	8.27				
0+50	36.75	10.51	18.31	4.52	18.31	4.52
1+00	26.94	19.48	58.97	27.77	77.28	32.29
1+50	17.14	29.01	40.82	44.90	118.10	77.19
1+78.56	11.54	34.71	15.17	33.70	133.27	110.90
2+00	0.10	65.43	4.62	39.76	137.89	150.66
2+01.65	2.14	58.48	0.07	3.79	137.96	154.44
2+25.42	0.00	100.72	0.94	70.08	138.91	224.52
2+50	0.00	134.32	0.00	106.99	138.91	331.51
2+60.42	0.00	0.03	0.00	25.92	138.91	357.43
2+75.42	0.00	131.20	0.00	36.45	138.91	393.88
			0.00	0.00	138.91	393.88

STREET	VOLUMES		CUMULATIVE VOLUMES	
	Cubic Yards		Cubic Yards	
	CUT	FILL	CUT	FILL
Rosewood	2255.00	97.24	2255.00	97.24
Woodcreek	1748.63	17.65	4003.63	114.89
Rosewood Ct (east)	138.91	393.88	4142.54	508.77
Rosewood Ct (west)	86.37	541.27	4227.91	1050.04

REVISED

Whispering Lakes Addition Cross Section Quantities WICHITA, KANSAS			
	Ruggles & Bohm, P.A. Engineering, Surveying, Land Planning		DESIGN CMB
	924 North Main Wichita, Kansas 67203 www.rbkansas.com		DRAWN EJC
	(316) 264-8008 (316) 264-4621 fax E-mail: info@rbkansas.com		REVIEW
	DRAWING FILE Paving {Xsec Quant}		PROJECT NUMBER 472-83668
DATE Jan. 21, 2003		UTILITY	REB JOB Z21E
			SHEET 30 OF 31