F O X R I D G E A D D I T I O N

RED FOX

SILVER HOLLOW

SILVER HOLLOW CT.

EXIST. VALVE BOXES
EX. VALVE BOX=166.80 NE
PROP. TOP EL.=167.40 NE
EX. VALVE BOX=166.70 SE
PROP. TOP EL.=167.40 SE
EX. VALVE BOX=166.70 NW
PROP. TOP EL.=167.40 NW

10' TRANSTION FROM FULL CURB TO ROLL CURB

CONST. 6" A.C. PAVEMENT W/5" CRUSHED ROCK BASE ON GEOGRID REINFORCEMENT

CONST. 4" SIDEWALK

CONST. COMBINED CURB AND GUTTER, ROLL 3 5/8"

10' TRANSTION FROM ROLL CURB TO FULL CURB

INSTALL SNS Silver Hollow/ Silver Hollow Ct 9003–9039

INSTALL 7" REINF. CONC. VALLEY GUTTER W/5" CRUSHED ROCK BASE ON GEOGRID REINFORCING.

ADJUST EXIST. VALVE BOX
EX. VALVE BOX EL.=167.40
PROP. TOP EL.=167.70

CONST. MEDIAN CURB & GUTTER

SCALE: 1"=20'

RESERVE "R"

STA. 4+79.04 BL#1 END 4" SIDEWALK

INSTALL CURB INLET SEDIMENT BARRIER

INSTALL HAYBALE SEDIMENT BARRIER

STA. 4+82.00 BL#1 INSTALL E.O.R. MARKER

GRADE THIS AREA AS NECESSARY TO DRAIN INTO INLET OPENINGS (SUBSIDIARY TO PROJECT)

STA. 4+88.00 BL# 1 INSTALL E.O.R. MARKER

ADJUST EXIST. SSMH TOP
EXIST. TOP EL.=167.70
PROP. TOP EL.=167.20
FL=156.41

EXIST. SSMH TOP
TOP EL.=168.32
FL=153.86

P.V.I. ELEV. = 168.31 NO V.C.

P.V.I. ELEV. = 167.39 NO V.C.

LEGEND

STREET SIGN & SIGN LOCATION (SEE SIGN ASSEMBLY TABLE FOR TYPE & STATION OF SIGN)

G:\CIVIL\99118\DWG\PAV\PH_2\99118E3.DWG

MKEC ENGINEERING CONSULTANTS
411 N. WEBB ROAD
WICHITA, KS. 67206
316 - 684 - 9600

FOX RIDGE ADDITION
PROJECT NAME

SILVER HOLLOW - PHASE 2
SHEET TITLE

DK	DM	DK
DESIGN BY:	DRAWN BY:	CHECKED BY:
SEPTEMBER 2003	99118E3	11 / 24
DATE	JOB NO.	SHEET/OF