



- = Inlet Sediment Barrier
- ⊠ = Minimum Areas for Silt Fence
- ▨ = Easements To Be Graded
- ⌒ = Hay Bale Barrier

Approximate Easement Grading Quantities:
 (For Information Only)
 Excavation: 731 C.Y.
 Fill: 4,030 C.Y.

The contractor shall grade the easements as shown to the elevations given on the easement grading plan. All costs for grading shall be incidental to the Easement Grading Bid Item.

The contractor shall 'straight' grade the easements between the elevations given. Where a callout designates 'Match', the contractor will grade to the existing ground elevation.

Install silt fence barriers per detail.

Install hay bale barriers per detail, sheet 19.

Install silt fence barriers per detail.

Install hay bale barriers per detail, sheet 19.

		STEVE KELLEY 5TH ADDITION	
		ESMT. GRADING PLAN STREET IMPROVEMENTS	
Baughman Company, P.A. 315 Ellis St. Wichita, KS 67211 P 316-262-7271 F 316-262-0149 ENGINEERING SURVEYING PLANNING LANDSCAPE ARCHITECTURE		DESIGN	DRAWN
PROJECT NUMBER	472-83993	MWS	TMS
APPROVED		DATE	06/04
REVISIONS:		SCALE	Noted
		SHEET	18 OF 25