Contractor to Install Approx. 200 L.F.* of Silt Fence or Straw Bale Ditch Checks as Necessary. See Details, Sheets ___.

SCALE: 1" = 40'

Erosion Control Blanket

Light Stone Rip Rap

Silt Fence/Straw Bales Ditch Checks

*For Information Only. Cost to be INCIDENTAL to "Erosion Control".

**For Information Only. Cost to be INCIDENTAL to "Site Restoration".

MINNESOTA AVENUE

25' UTILITY EASEMENT

GEORGIA AVENUE

WINNEBAGO

BALCH HOMESTEAD ADDITION

10' UTILITY EASEMENT

16' UTILITY EASEMENT

20' DRAINAGE EASEMENT

124.27'

124.05'

123.86'

123.69'

143.58'

170.56'

159.31'

125.36'

74.40'

65.40'

63.44'

90.06'

50.40'

29.39'

31.36'

74.07'

24

23

22

21

20

19

BLK 1

16'

8'

Water Level

Top of Bank

Pond Bottom

Proposed 35' Drainage Channel

60' DRAINAGE EASEMENT

RIVERSIDE MOBILE HOME PARK

EMERY PARK
BOARD OF PARK COMMISSIONERS
C-101-UP

The Erosion Control Blanket Shall be Curlex/Excelsior, or approved equal. Install per manufacturers recommendation, including staples. See Detail, Sheet 18.

Light Stone Rip Rap is to be placed from Elevation 72.00 to 76.00. See Pond Detail, Sheet 8.

Erosion Control Quantities Required for this Sheet:

Light Stone Rip Rap	3780 S.Y.
Erosion Control Blanket	4030 S.Y.*
Reseeding	1 Acre**

Ex. 8' Chain Link Fence

Ex. Sprint Fiber Optic Cable

KANSAS TURNPIKE AUTHORITY

EOA

Ex 24' Drainage Channel and Trash Grate

Double 10' x 4' RCBC

Ex 4' Chain Link Fence

PROJECT NUMBER	SHEET NAME	ENGINEERING DIRECTORY
472-76-245-83324	Pond Erosion	F:\\Hydraulic\Pond

DESIGN	DRAWN	APPROVED	DATE	SCALE	BAUGHMAN NO
TPV/JFB	TPV	JFB	Sept 2001	Noted	99-09-E453

CAPITAL IMPROVEMENT PROJECT

POND EROSION CONTROL PLAN

HYDRAULIC AVENUE PAVING - INCIDENTAL DRAINAGE PROJECT - PHASE 2

BAUGHMAN COMPANY, P.A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 * 315 ELLIS * WICHITA, KANSAS 67211