SCALE: 1" = 20'

HENRY P. ALCARAZ
B - 12517
5

JIMMIE D. COSTLOW
Revocable Trust
B - 12516
3

CHARLES F. SIMONSEN
B - 12515
1

CHARLES L. & JEANENE S. HUDDLESTON
B - 12419
6

GEORGE W. & PATRICIA M. KNOWLES
B - 12418
5

Sta 118+60 Left/Right Match Existing Pavement Markings & Begin Phase I Marking and Signing

Sta 119+18.6 Match Exstg Markings

Sta. 120+00.0 31' Lt. Install S1-1 per Detail See Sheet 67.

Sta. 120+69.00 End Transition Begin 48.0' FF Pavement Section

Sta. 121+92.5 48' Lt. Install R1-1 per Detail See Sheet 67.

Sta. 122+42.0 31' Lt. Install SNS per Detail See Sheet 67.

Sta. 123+61.7 31' Rt. Install SNS per Detail See Sheet 67.

Sta. 124+16.2 55' Rt. Install R1-1 per Detail See Sheet 67.

S1-1 36" X 36"

R1-1 30" X 30"

STOP

Transition 7.0' in 209.0'

Transition 5.17' in 209.0'

46TH STREET

46TH ST SOUTH

FERNWOOD

60.00' R/W

64.00' R/W

50.00' R/W

40.00' R/W

30.00' R/W

46th Str 1600 E
D-3 METRO
Size Varies
(See Dtl Sheet)

Hydraulic 4600 S
D-3 METRO
Size Varies
(See Dtl Sheet)

Fernwood 1700 E
D-3 METRO
Size Varies
(See Dtl Sheet)

Hydraulic 4600 S
D-3 METRO
Size Varies
(See Dtl Sheet)

12" Yellow @ 30'

4" Dbl Yellow 4"-4"-4" Typical Spacing

6" White

21.88' Nominal

80.00' Nominal

84.95' Nominal

SNS

R25' Fc

Ex Curb & Gutter

Ex Walk

Conc Drv

Bush

Tree

Guy

40" Tree

26" Pine

SSMH

SSMH 5542-J68

TSIG

LP

MBx

JBx

HLP

PP

#X Rebar

161.29'

208.7'

148.5

133.5

136

120

SCOTT STUCKEY
Revocable Trust
C - 49 - 1E - UP

FLOYD A. & JAN LEE
McBRIDE
C - 50 - UP

EFFIE STUCKEY
Living Revocable Trust
C - 49 - 1G - UP

SCOTT & EFFIE STUCKEY
C - 49 - 1H - UP

PROJECT NUMBER	SHEET NAME	ENGINEERING DIRECTORY
472-76-245-83324	MARK01	F:\Eng\Hydraulic\Traffic

DESIGN	DRAWN	APPROVED	DATE	SCALE	BAUGHMAN NO
JFB	STAFF	JFB	Sept. 2002	Noted	99-09-E450

CAPITAL IMPROVEMENT PROJECT

PAVEMENT MARKING PLAN

HYDRAULIC AVENUE PAVING - 47TH STREET SOUTH TO MACARTHUR ROAD

BAUGHMAN COMPANY, P.A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 • 315 ELLIS • WICHITA, KANSAS 67211