SCALE 1"=20'

STA 3+50 | STA 4+00 | STA 4+50 | STA 5+00 | STA 5+50 | STA 5+80 | STA 6+00.79

MATCH LINE

HOUSE | BUSH | 4" CH. LK. FC. | CONC. WK. | 24" TREE | R/W 25' | 5" CH. LK. FC. | 5"-12" TREE ROW | 12" TREE | 6" TREE | BUSH | P.P. | STUMP | R/W 30

1 1/2"-1" BROKEN ASPH. PATCH

GETTO AVE.

BROKEN ASPH.

CONC. DR. ENTRANCE FROM VOLUTSIA

305.00'

IRON IN THIMBLE @ CL 15TH ST. NO. & VOLUTSIA

VOLUTSIA

CONC. PVMT.

SCALE 1"=20'

STA 6+60.72 | STA 6+80 | STA 7+00 | STA 7+50 | STA 8+00 | STA 8+30 | STA 8+48.21 | STA 8+70.37 | STA 9+15 | STA 9+34.78

MATCH LINE

R/W 30 | 6" TREE | 8"-12" TREE ROW | HOUSE | TREE ROW & BARB WIRE FC. | R/W 25' | G.M. | 8" TREE | CONC. WK. | 4" CH. LK. FC. | CONC. DR. | P.P.

1 1/2"-1" BROKEN ASPH. PATCH

GETTO AVE.

ERIE

AREA TO BE REMOVED. THE COST OF SAW CUT IS SUBSIDIARY TO OTHER BID ITEMS.

B.M. 133.09 "X" TOP OF CB. ON W. SIDE ESTELLE & S.L. 14TH NO.

TEMP. B.M. 1, 132.58 "+" TOP CB. W. SIDE ESTELLE ON NL GETTO

TEMP. B.M. 3, 126.54 "+" TOP CB. 3' W. EL GREEN ON S. SIDE OF GETTO

TEMP. B.M. 5, 136.87 "+" TOP CB. 4' E. WL VOLUTSIA ON S. SIDE GETTO

TEMP. B.M. 7, 142.78 "+" TOP CB. NE COR. ERIE & GETTO, @ SE COR WCR RUNNING N-S

GETTO ST. CLOSURE
TOPO & REMOVAL PLANS
INDEX # 617555
SHEET 3 OF 11
DRAWN: B.R. DESIGN: B.R.