FHWA REGION NO.	STATE	PROJECT NO.	FISCAL YEAR	SHEET NO.	TOTAL SHEETS
		*	1983	9	37

*CITY OF WICHITA PROJECT NO. 472-76-245-8119-000-000-001

FINAL SURVEY	NOTE BOOK	NO.	SURVEYED	PLOTTED	CHECKED	AREAS	AREAS CHECKED	BY	DATE

ORIGINAL SURVEY	NOTE BOOK	NO.	SURVEYED	PLOTTED	CHECKED	AREAS	AREAS CHECKED	BY	DATE

100.00' @ + 0.32%
NORTH CURB

200.00' @ -0.49%
NORTH CURB

150.00' @ +0.61%
NORTH CURB

50' VERTICAL CURVE

50' VERTICAL CURVE

10+00 BEGIN PERMANENT CONSTRUCTION NORTH
MATCH FLOWLINE @ 112.76 (±)

PVC 10+75 ELEV. 113.56

PVI 11+00 ELEV. 113.63

PVT 11+25 ELEV. 113.51

PVC 12+75 ELEV. 112.77

PVI 13+00 ELEV. 112.65

PVT 13+25 ELEV. 112.80

12+62.50 NORMAL CROWN

175'
SUPERELEVATION RUNOUT

14+37.50

MATCH LINE @ STA. 14+50

SUPERELEVATION RUNOFF

TOP NORTH CURB

TOP SOUTH CURB

MEDIAN NORTH FLOWLINE

MEDIAN SOUTH FLOWLINE

38.33' @ 1.02%

38.65' @ 1.68%

RETURN ELEV. 113.03 / 112.89

MID-POINT ELEV. 112.75

RETURN ELEV. 112.50

RETURN ELEV. 112.42 / 113.07

MID-POINT ELEV. 112.75

RETURN ELEV. 14+24.01

BEGIN PERMANENT CONSTRUCTION SOUTH 10+86
MATCH FLOWLINE @ 113.12 (±)

245.03' @ -0.32%
SOUTH CURB

25.99' @ 0.37%

DODGE STREET

LEGEND

EXIST. SOUTH TOP OF CURB
EXIST. NORTH TOP OF CURB
GROUND AT SOUTH PROPERTY LINE
NEW SOUTH TOP OF CURB
NEW SOUTH MEDIAN FLOWLINE
NEW NORTH TOP OF CURB
NEW NORTH MEDIAN FLOWLINE

SCALE

1" = 20' HORIZONTAL
1" = 1' VERTICAL

NOTE: FOR STORM SEWER SYSTEM SEE SHEET NO. 15

JOHN M. OSWALD LICENSED 7994 KANSAS PROFESSIONAL ENGINEER

WICHITA, KANSAS McLEAN AT SENECA INTERSECTION IMPROVEMENTS PROFILES FILE; 82-324A SHEET 9 OF 37