SCALE: 1"=20'

Remove Curb and Gutter and Pavement and Sidewalk within the Limits indicated by Hachures

Remove Inlet

Const. Limits

Spare Trees

Remove Sign

Spare Trees

1001

Remove Area Inlet

Remove Portland Cement Concrete Ring

Remove Retaining Wall completely and Sidewalk as noted by Hachures.

Remove Poles and Sign

Remove Water Meter and Concrete Vault. Cap existing pipe.

1264

1220

Spare Trees

Remove Totem Pole and Foundation. Salvage to a location designated on Indian Center Property and Re-install per Landscape Plans.

1016

Remove Flagpoles and Foundations

Salvage Poles to a location Designated on Indian Center Property and Re-install per Hardscape Plans.

Remove Yard Light and Base

Salvage to a location on Indian Center Property (Typical 7 locations)

Remove Sidewalk within the Limits indicated by Hachures

Remove Curb and Gutter and Pavement within the Limits indicated by Hachures

Remove Sprinkler Head

(Typical Approx. 12 locations) Salvage to a location designated on Indian Center Property See General Note

Const. Limits

Spare Trees

1217

Spare Trees

Spare Trees

Spare Trees

INDIAN CENTER

1001 Layout Control Point
#4 bar w/ PEC Cap set at point
See Sh. No. for Additional Information

BENCHMARK:
CHISELED "O" ON TOP OF CURB AT SOUTHWEST CORNER OF EXISTING PARKING BAY APPROXIMATELY 96 FEET WEST OF BUILDING. 9021 208N, 12485 685E
ELEV. =112.62

GENERAL NOTES

1. UNLESS OTHERWISE NOTED, OR DIRECTED AT THE TIME OF CONSTRUCTION, REMOVE ALL TREES WITHIN THE CONSTRUCTION AND HAUL OFF SITE TO AN APPROVED DISPOSAL AREA.
2. ALL SPRINKLER HEADS LOCATED WITHIN THE CONSTRUCTION LIMITS SHALL BE REMOVED. LINES INTERRUPTED BY THESE REMOVALS WHICH CONNECT TO LINES TO REMAIN SHALL BE CAPPED OR SPLICED AS APPLICABLE. NO SEPERATE PAYMENT WILL BE MADE FOR THIS WORK AND IT SHALL BE CONSIDERED INCIDENTAL TO OTHERS ITEMS OF DEMOLITION.
3. REMOVAL OF CURB AND GUTTER AND PAVEMENT CONTIGUOUS TO EXISTING ENTRANCE SHALL BE DELAYED UNTIL THE NEW ENTRANCE IS COMPLETE AND OPERATIONAL.

   DEMOLITION OF PAVEMENT AROUND THE TOTEM POLE SHALL BE DELAYED UNTIL WORK IN THIS AREA CAN BE COMPLETED WITHOUT DELAY OR INTERRUPTION.
4. UNLESS OTHERWISE NOTED, ALL MATERIAL REMOVED SHALL BE HAULED OFF SITE AND DISPOSED OF AT AN APPROVED LOCATION.
5. SEE SH. NO. TS-1 FOR ADDITIONAL REMOVAL ITEMS.

PLAN

NOTE BOOK	SURVEYED	BY	DATE
NO	PLOTTED		
	ALIGNMENT CHECKED		
	RT OF WAY CHECKED		

DRAWING NAME: 36-92005 JC DEMO
LOCATION: 04 #738 AND 739
CENTER COORDINATES:
ROTATION ANGLE:
DATE LAST WORKED ON: SEPT. 22, 1994
BRENT REMSBERG

REV.	DATE	DESCRIPTION

BRENT E. REMSBERG LICENSED 8166 KANSAS PROFESSIONAL ENGINEER

HELLMUTH, OBATA & KASSEBAUM, INC.
DALLAS, TEXAS

PROFESSIONAL ENGINEERING CONSULTANTS, P.A.
WICHITA, KANSAS

BRAD J. GOLDBERG
DALLAS, TEXAS

MID-AMERICA ALL-INDIAN CENTER SITE IMPROVEMENTS CITY OF WICHITA, KANSAS

DEMOLITION PLAN

PROJECT NO.	ISSUE DATE	SCALE	SHEET
		1"=20'	D-1