NOTES:

1. All embankment material to be placed in median to be Select Soil.
2. Contractor to resod all disturbed areas outside of designated sodding limts.
3. Top 150 mm of all embankments west of Hillside to be Select Soil.

Scale: 1 : 200

EXIST. TREES TO BE PRESERVED
THINNING SHALL BE REQUIRED
& DETERMINED IN THE FIELD BY L.A. (TYP)
(COST SUBSIDIARY TO PROJECT)

INSTALL 1.8 M CHAINLINK FENCE (TYP
(REFER TO REQUIREMENTS SHEET 37)

College Terrace Addition
Block 4

1 M (TYP)

PROJECT LIMITS

INSTALL 18" DRAIN BASIN
INLET TOP=52.5
FLOW=51.70

Shadybrook Addition
Block 16

PROPOSED UTILITY PAD
(BY OTHERS)

STADIUM

Shadybrook Addition
Block 13

INSTALL 16.50 m
OF 12" PIPE @ 2%

INSTALL 18" BASIN
SOLID TOP=53.00
FLOW=51.50

INSTALL 16.50 m
OF 12" PIPE @ 2%

300 mm PIPE
(FL. IN=51.50)

R/W = Ex. Property Line
32.994 m (65') Sec. Line

1.8 m Sidewalk

HILLSIDE

HILLSIDE

0+400

℄ Prop. Impr. = Section Line

PROJECT LIMITS

Exist. R/W
9.144 m (30') S.L.

Exist. R/W
9.144 m (30') S.L.

TW=6.5

TW=5.7

TW=5.0

TW=4.4

TW=4.4

TW=3.7

TW=4.3

TW=4.8

Match

Match

Match

MATCHLINE
(SHEET 29)

MATCHLINE
(SHEET 31)

Wichita State University

LEGEND

- 2 m Grid
- Sodding Limits
- 59.0 Proposed Grading Contour
- Tree to be removed
- Slope Arrow

H:\CIVIL\01053\PAVE\01053RS2.DWG 05/01/03 02:41:24 PM CDT

ROADSIDE IMPROVEMENTS
STA. 0+320 TO STA. 0+480

PROJ. NO. 472-83537 SEDGWICK CO.

MKEC ENGINEERING CONSULTANTS, INC.
WICHITA, KANSAS

DESIGNED BY:	MKEC	CHECKED BY:	MKEC
DRAWN BY:	BJH	DATE: 04/03	SHEET 30 OF 73