

GENERAL NOTES:

- Utility service lines, poles, valve boxes, meters and etc. are to be adjusted as necessary by others prior to construction unless the plans specifically call for their adjustment by the Contractor. Existing utilities and their location, as shown on the plans, represent the best information obtainable for design. The Contractor will be required to work around existing utilities within the right-of-way which do not conflict with proposed construction.
- The Contractor shall provide a minimum of forty-eight (48) hours advanced notice to all utility owners prior to work in any area where existing utilities will be uncovered to allow the utility owner to inspect uncovering of their utility. Any utility carelessly damaged by his construction operations shall be repaired or replaced at no extra cost to the City. The Contractor shall coordinate work with contractors for utility companies and other agencies for minimum inconvenience to the general public.
- The Contractor shall coordinate the tie back, protection of power poles, light poles and appurtenances with KG&E. Two weeks notice to KG&E is required.
- The top elevation of inlets, inlet manholes and manholes as shown on the drawings may vary to meet existing or proposed pavements or top of curb elevations. The Engineer may adjust the locations and flowlines of storm sewers, inlets, inlet manholes and manholes with references to existing or proposed paving plans of the pertinent street.
- A saw cut of at least one-half the depth of existing surface courses or one-fourth the depth of the existing total pavement thickness shall be provided at locations where proposed construction abuts an existing surface course or pavement for which partial removal of that surface or pavement is required. Sawed joint to facilitate removal within three (3) feet of existing joints will not be permitted and for such instances the limits of removal shall extend to the existing joint. Such saw cuts will not be paid for directly and this cost shall be considered as subsidiary to the project cost.
- Rubble from the removal of miscellaneous structures and excess excavation which is to be wasted shall be disposed of on sites to be provided by the Contractor. These sites shall be approved by the Engineer as to suitability, appearance, and site location. Locations that, in the opinion of the Engineer, will leave an unsightly appearance will not be approved.
- Trees and shrubs in public right-of-way which are in direct conflict with proposed construction shall be removed by the Contractor with the Engineer's approval. Trees and shrubs which are not in direct conflict with the proposed new construction shall be saved and protected from damage.
- Limits of earthwork shall match existing ground elevations at the right-of-way line unless otherwise noted on the plans with a new finished grade elevation. When a new finished grade elevation is shown, the earthwork shall extend one foot beyond the right-of-way line and then slope up or down using permissible slopes to match existing ground surfaces.
- The Contractor shall be responsible for preserving property irons. The Contractor will be required to reestablish any property irons which are damaged or destroyed by his construction operations. Such irons shall be reestablished by a licensed land surveyor or a licensed professional engineer in accordance with state laws.
- Curb return top of curb elevations indicated on the drawings are shown at the quarter points of the return.
- The Contractor shall seed, fertilize and mulch all disturbed areas within the construction limits in accordance with the plans and specifications.
- The Contractor shall comply with all applicable safety regulations, insuring safety of personnel directly involved with the project and insuring the safety of the public shall be the Contractor's responsibility.
- Right-of-way stationing shown on the plans depicts plat distances. No legal survey has been made to verify these dimensions.
- Concrete for all 6" portland cement concrete base, combined curb and gutter, 8" concrete pavement (including alleys) and 6" concrete pavement (driveways) shall conform to the requirements for handling of materials, mixing and placing construction joints and concrete finishing specified in Division 400 and Division 500 of the Standard Specifications, except that the mixed concrete shall contain a minimum of 733 of 733 pounds of Type II cement per cubic yard and the final pavement surface shall be burlap drag and broom finish instead of the transverse grooved surface in said Division 500. This cement quality shall apply to all the aggregate combinations permitted in said Division 400. Protection and curing of concrete shall be as specified in said Division 500.
- All concrete pavement, combined curb and gutter and concrete base courses constructed with concrete having a minimum cement content of 733 pounds per cubic yard may be opened to use by motorized traffic at the end of a period of 4 days. Flexural strength will not be a condition for opening sections of such pavement to motorized traffic.
- Widened gutter section of combined curb and gutter at intersections will not be paid for directly, and this cost shall be considered a subsidiary to TYPE I AND TYPE III CURB AND GUTTER.
- Concrete base widening shall be paid as square yards of Portland Cement Concrete Base (6" uniform).
- All salvageable drainage pipes, manhole rings and covers, and inlet grates and frames shall be carefully removed and stockpiled at locations within the right-of-way, as directed by the Engineer, for removal by City personnel.
- Unless otherwise indicated on the plans, backslopes shall be warped around new inlet construction as directed by the Engineer.
- The Contractor will be required to provide a minimum advance notice of forty-eight (48) hours to each of the following utility companies prior to the beginning of construction and request that any existing lines be flagged:

Kansas One-Call
(For exact location of all underground utilities)
1-800-344-7233
316-687-2470 (local Wichita)

People's Natural Gas
3845 W. Harry
Wichita, Kansas 67213
Jerry Watkins
316-942-8350
316-946-0096 (for emergencies)

KG&E, The Electric Company
1900 E. Central
Wichita, Kansas 67214
Don Morgan
316-261-6434

Conoco Pipe Line Company
8001 Oak Knoll
Wichita, Kansas 67207
Water: Dick McClintock
316-268-4555
Sanitary & Storm Sewer: Steve Palmer
316-268-4210
Sewage Treatment Plant #2 Superintendent: James Tush
316-529-9900


City of Wichita
455 N. Main
Wichita, Kansas 67202
Water: Dick McClintock
316-268-4555
Sanitary & Storm Sewer: Steve Palmer
316-268-4210
Sewage Treatment Plant #2 Superintendent: James Tush
316-529-9900

Southwestern Bell Telephone Company
154 N. Broadway
Wichita, Kansas 67202
Greg Sharpe
316-268-2245

Williams Brothers Natural Gas
4000 S. Seneca
Wichita, Kansas 67217
Doug Wilson
316-945-0220
Bill Hagaman
316-524-4390

KP&L Gas Service
1021 E. 26th Street North
Wichita, Kansas 67219
Calvin Brummer
316-832-0012

Multimedia Cablevision
701 E. Douglas
Wichita, Kansas 67202
Don Shue
316-262-4270



GENERAL NOTES

Rock Base Is To Be Compacted And Smoothed With A Steel Faced Roller Prior To Placement Of Asphalt. Tack Coat Will Not Be Applied To Rock Base.

A Tack Coat Of Emulsified Asphalt (SC-1H Or CSS-1H) Shall Be Applied At An Approximate Rate Of 0.05 Gallons Per Square Yard Between Each Lift Of Asphaltic Material.

Bituminous Base And Asphaltic Concrete Wearing Surface Shall Be Placed With A Laydown Machine Having Automatic Controls For Line And Grade.

Construction Joints In Each Lift Shall Be Staggered A Minimum Distance Of One (1) Foot From Joints In Preceding Lifts And Placed So That A Joint Will Be Constructed On The Centerline Of The Top Lift.

Description		
K-42/Pawnee Ave/West St General Notes/Typical Sections		
Scale:	Drawn By: SAC	Index No.: 706028
Date: Nov 1994	Revised: Mar 95	
CITY OF WICHITA DEPARTMENT OF PUBLIC WORKS ENGINEERING DIVISION City Engineer - Michael E. Lindebak		