


HASKELL ST

HASKELL CY Excavation (unadjusted)				HASKELL CY Compacted Fill (unadjusted)				HASKELL CY Loose Fill (unadjusted)			
Station	Area	Volume	Total	Station	Area	Volume	Total	Station	Area	Volume	Total
0+55.18	12.95	0.00	0.00	0+55.18	1.26	0.00	0.00	0+55.18	13.25	0.00	0.00
1+00	12.96	21.51	21.51	1+00	1.26	2.09	2.09	1+00	13.25	22.00	22.00
1+50	12.96	24.00	45.51	1+50	1.26	2.33	4.42	1+50	13.25	24.54	46.54
1+96	12.96	22.08	67.59	1+96	1.26	2.14	6.56	1+96	13.11	22.45	69.00
2+30	29.17	26.52	94.11	2+30	0.00	0.79	7.35	2+30	0.00	8.25	77.25
2+64.30	12.96	26.76	120.87	2+64.30	1.26	0.80	8.15	2+64.30	13.24	8.41	85.66
3+00	12.96	17.14	138.01	3+00	1.26	1.59	9.75	3+00	13.25	17.56	103.22
3+50	12.96	24.00	162.02	3+50	1.26	2.23	11.98	3+50	13.25	24.61	127.83
3+95.77	12.96	21.98	183.99	3+95.77	1.26	2.13	14.11	3+95.77	13.25	22.47	150.30



**BAUGHMAN  
COMPANY**

315 Ellis St.  
Wichita, KS 67211  
316-262-7271  
BaughmanCo.com

TURKEY CREEK 4TH ADDITION  
PHASE 1A

**EARTHWORK  
CROSS  
SECTIONS**

Street Paving Improvements

PROJECT NUMBER:  
472-2020-085617

DESIGN: DMV DRAWN: JAK

DATE: Apr. 2, 2021

SHEET OF  
**16 22**

File: E:\Projects\Turkey Creek 4th\_1\Engineering\Phase 1A\Str\_20-01-E457\STR PLANS.dwg