



* Side Street Inlet Hookups are Future Construction and not a part of this project unless specifically stated.

ALT. I:
Const. 10" Valley Gutter
6" Reinf. Conc. & 4" A.C. Base
ALT. II:
Const. 6" Reinf. Conc. Valley Gutter
On 10" Reinf. Crushed Rock

SEWER MANHOLE ADJUSTMENT			
STA	OFFSET	EXIST. ELEV.	PROP. ELEV.
39+68	6'L	84.08	83.13
41+68	6'L	84.09	83.73
42+88	6'L	84.30	84.12

WATER VALVE BOX ADJUSTMENT				
STA	OFFSET	EXIST. ELEV.	PROP. ELEV.	NOTES
37+72	55'R	83.00	83.28	WV/FH
37+75	42'R	82.60	83.10	
38+71	40'R	83.43	83.92	Air Release
40+86	45'R	--	83.52	
41+03	55'R	82.83	83.61	
41+71	40'R	83.16	84.09	Air Release

SOUTH SENECA IMPROVEMENTS

PAVING PLAN

55TH ST. SO. TO 48TH ST. SO.

MID-KANSAS ENGINEERING CONSULTANTS PA
3500 NORTH ROCK ROAD
BUILDING #800
WICHITA, KANSAS 67226

DCH
DLM
DLM
OCT. 1989
10
58