

[illegible]

EDGE CURB (6") (AE)	
LOCATION	EDGE CURB 6" (AE)
STA. 40+41.12 BROOKVIEW	L.F. 42.3 (N) 42.3 (S)
TOTAL	85.0

CONC. PAVEMENT (8"-UNIF.) (AE) (NRD J)			
NAME	STATION	SIDE	CONC. PVMT (8"-UNIF.) (AE) S.Y.
BROOKVIEW	42+41.12	L.T.	234.8
TOTAL			235

CONC. PAVEMENT (6"-UNIF.) (AE) (PL)					
STATION	SIDE	TYPE	WIDTH (W) L.F.	LENGTH (P) L.F.	CONC. PVMT (6"-UNIF.) (AE)
					S.Y.
36+90.5	RT.	RR	12	25.5	37.6
37+73.3	RT.	RR	12	25.5	37.6
TOTAL					75.2

ADJUSTMENT OF MANHOLES			
STATION	SIDE	MANHOLE ADJUSTMENT	
		TYPE B	TYPE C
35+73	L.T.	1	
36+77	R.T.	1	
40+11	L.T.	1	
44+53	L.T.	1	
TOTAL		4	

RECAPITULATION OF ROAD QUANTITIES		
ITEM	UNIT	TOTAL QUANTITY
CLEARING AND GRUBBING	L.S.	L.S.
REMOVAL OF EXISTING STRUCTURES	L.S.	L.S.
COMMON EXCAVATION	C.Y.	5,840
ROCK EXCAVATION	C.Y.	1,127
COMPACTION OF EARTHWORK (TYPE B) (MR-90)	C.Y.	3,300
CRUSHED STONE SUBGRADE (7.5")	S.Y.	7,808
GEOGRID REINFORCEMENT (FOR BASE)	S.Y.	7,808
WATER (GRADING) (SET)	M. GAL	1
18" STORM SEWER (RCP)	L.F.	109
24" STORM SEWER (RCP)	L.F.	1,176
CURB INLET (TYPE 1-A)	EA	6
ADJUSTMENT OF MANHOLES	EA	4
ADJUSTMENT OF CATCH BASIN	EA	1
COMBINED CURB & GUTTER (AE)	L.F.	2,531
EDGE CURB (6") (AE)	L.F.	85
SIDEWALK CONST. (4') (AE)	S.Y.	1,840
CONC. PAVEMENT (6") (AE) (PL)	S.Y.	75
CONC. PAVEMENT (8") (AE) (PL)	S.Y.	78
CONC. PAVMENT (8") (AE) (NRDJ)	S.Y.	235
CAST IRON	LB.	420
Foundation Stabilization (Set)	C.Y.	1
MOBILIZATION	L.S.	L.S.
TEMPORARY SURFACING MATERIAL (Set)	C.Y.	1
FIELD OFFICE & LAB, TYPE A	Ea.	1
MOBILIZATION (DBE)	L.S.	L.S.
Construction Staking by L.P.A.		
FOR CONSTRUCTION TRAFFIC CONTROL QUANTITIES, SEE SHEET ____ 27 ____		
FOR BITUMINOUS SURFACING QUANTITIES, SEE SHEET ____ 19 ____		
FOR SEEDING QUANTITIES, SEE SHEET ____ 21.A ____		
FOR PAVEMENT MARKING QUANTITIES, SEE SHEET ____ 24 ____		
FOR DRAINAGE STRUCTURES SUMMARY, SEE SHEET ____ 16 ____		
FOR LANDSCAPE QUANTITIES, SEE SHEET ____ 30 ____		
FOR WINTER POLLUTION CONTROL (SOIL EROSION), SEE SHEET ____ 29 ____		

<i>WOODLAWN AVENUE</i>		
<i>SUMMARY OF QUANTITIES</i>		
SCALE:	APPROVED:	DRAWN BY:
DATE:		CHECKED:
PROJECT NO.:		SHEET NO.: