Note #1 Westar Conduit
Existing Westar conduit and manholes to be abandoned by Westar Energy. City of Wichita to assume ownership of conduit and manholes on south side of Douglas. Light pole bases to be removed by others.

Note #2 Service Box Lids
Remove service box lids at NE and SE corner of intersection of Douglas and Seneca, replace with lids to be picked up at CMF 1801 S. McLean.

Note #3 Trench Backfill
All trench backfill for this project will be jetted and flushed sand as per City of Wichita specifications. Flowable fill is not required.

** Offset dimension for Inlets are measured from the inside face of the box structure nearest the curb to the centerline of the street right of way*

20 0 10 20 40 80
(IN FEET)
1 inch = 20 ft.

No.	Description	Northing	Easting	Station	Offset	Elevation
8	X cut in Sidewalk NW Cor. Seneca & Douglas	5000.01	10000.02	9+59.97	50.38 L	112.99
9	X cut in Sidewalk NW Cor. Douglas & Walnut	5011.06	10345.59	13+05.59	59.99 L	112.93
10	PK nail in Asph. Parking Lot SE Cor Douglas & Handley	4897.39	10787.61	17+47.13	55.52 R	112.97
11	X cut Concrete Parking Lot NW Cor Douglas & Osage	5010.42	11056.55	20+16.94	56.39 L	113.24
12	5/8" rebar SE Cor Douglas & Oak	4901.36	11416.44	23+75.97	54.16 R	112.60
13	PK nail Asphalt Parking Lot NW Cor Seneca & Sycamore	5015.72	11758.92	27+54.31	58.02 L	111.81
14	X cut in SW at NE Cor Nichol's Honda	5226.83	12268.81	32+95.18	51.58 R	110.96

BL Sta 11+40.08 36.87' Lt.
Light Fixture

Construct 24' Concrete Drive Approach (See Detail Sheet CV 4.9) 539 S.F. 8" Reinf. Conc.

Sta 10+87.23 Lt. match curb to be built with Seneca project

Sta 10+87.23 Begin construction, match existing concrete joint

Construct 24' Concrete Drive Approach (See Detail Sheet CV 4.9) 456 S.F. 8" Reinf. Conc.

Planter Drains See Arch. Plans

KGE MH. See note 1 Sheet CV 1.1

Existing conduit to be abandoned by Westar Energy.

Construct 19' Concrete Drive Approach (See Detail Sheet CV 4.9) 435 S.F. 8" Reinf. Conc.

KGE MH. See note 1 Sheet CV 1.1

BL Sta 12+26.08 36.51' Lt.
Light Fixture

BL Sta 12+89.80 Lt.
Type 2 Curb Inlet
Top=112.44
FI(E)=108.63
FI(S)=108.88
FI 4" Stub (N)=109.21

Sta 45+58.50 Sawcut & Match Exist. Pavement.

BL Sta 13+04.63 39.40' Lt.
Light Fixture

BL Sta 13+64.45 Lt.
5'ø RCMH
Top=112.97
FI(E)=108.40
FI(W)=108.40
FI(N)=108.65

BL Sta 50+55.35 Rt.
Type 2 Curb Inlet
Top=112.74
FI(SE)=108.77

Construction Limits

BL Sta 14+15.41 38.10' Lt.
Light Fixture

KGE MH. See note 1 Sheet CV 1.1

BL Sta 14+20.49 Lt.
Type 2 Curb Inlet
Top=112.60
FL(S)=109.01
FL 4" Stub (N)=109.18

BL Sta 14+32.88 Lt.
5'ø RCMH
Top=112.72
FL(N)=108.95
FL(S)=108.95
FL(E)=108.20
FL(W)=108.20

Construct 14' Concrete Drive Approach (See Detail Sheet CV 4.9) 220 S.F. 8" Reinf. Conc.

Sawcut & Match Existing Pavement

KGE MH. See note 1 Sheet CV 1.1

BL Sta 15+01.26 38.10' Lt.
Light Fixture

KGE MH. See note 1 Sheet CV 1.1

BL Sta 14+76.99 38.10' Rt.
Light Fixture

Sta 14+86.43 40.38' Rt.
Exist. KGE MH to remain
No adjustment required
Replace KGE MH Lid w/
City of Wichita MH Lid

BL Sta 14+32.88 Rt.
Type 2 Curb Inlet
Top=112.68
FL(N)=109.15
FL 4" Stub (S)=109.68

Construct 18' Concrete Drive Approach (See Detail Sheet CV 4.9) 275 S.F. 8" Reinf. Conc.

BL Sta 10+99.80 37.70' Rt.
Light Fixture

BL Sta 11+85.80 38.10' Rt.
Light Fixture

Planter Drains
See Arch. Plans

Sta 44+50.93 Sawcut & Match Exist. Pavement.

Sta 13+45.00 Douglas=
Sta 45+00.00 Walnut

Concrete intersection. See sheet CV 4.7 for details.

Construction Limits

Sta 11+42.74 40' Rt.
Exist. KGE MH to remain
No adjustment required
Replace KGE MH Lid w/
City of Wichita MH Lid

Existing conduit to be abandoned by Westar Energy. City of Wichita to assume ownership.

Sta 12+55.53 40.38' Rt.
Adjust MH Lid
Top=112.81
Replace KGE MH Lid w/
City of Wichita MH Lid

BL Sta 12+59.80 38.1' Rt.
Light Fixture

BL Sta 12+74.74 Rt.
Type 2 Curb Inlet
Top=112.66
FI(N)=109.12
FI 4" Stub (S)=109.66

Sta 13+68.55 40.68' Rt.
Adjust MH Lid
Top=112.57
Replace KGE MH Lid w/
City of Wichita MH Lid

BL Sta 13+77.07 36.64' Rt.
Light Fixture

Remove

Mill and Overlay

Concrete Intersection Pavement
See Detail Sheet CV 1.7

6" Asphalt Pavement
See Detail Sheet CV 1.7

kemiller engineering
516 S. Market,
Wichita, KS 67202
316/264-0242

CITY OF WICHITA

McCLUGGAGE VAN SICKLE & PERRY
ARCHITECTS PLANNERS LANDSCAPE ARCHITECTS
125 S. WASHINGTON WICHITA, KANSAS 67202
P.O. BOX 346 WICHITA, KANSAS 67201
PH. 316/262-6446 FAX 316/262-6445

WEST DOUGLAS STREETSCAPE
ARKANSAS RIVER TO SENECA
WICHITA, KANSAS

PAVING PLAN 1

PROJECT NO. 472 83608 OCA: 706846
MVP PROJECT NO. 101008
DATE: August 7, 2002
REVISED August 30, 2002

SHEET
CV 1.1