(IN FEET)
1 inch = 20 ft.

MATCH LINE Sta 15+50

MATCH LINE Sta 20+00

DOUGLAS AVENUE

WEST WICHITA

Sta 16+81.48 18.70' Lt.
Install 1-5' ø RCMH
Top=112.30
FL(W)=107.70
FL(E)=107.70
FL(N)=108.45

Sta 60+55.07 17.48' Lt.*
Install 1-Driveway Grated Inlet
Top=111.93
FL(E)=108.69
FL(S)=108.59

55+49.00 Sawcut & Match Exist. Pavement.

Sta 60+54.93 19.95' Rt.*
Install 1-Type 1 Inlet
Top=112.42
FL(W)=108.85

Construct 15' Concrete Drive Approach (Sheet CV 4.9)
234 S.F. 8" Reinf. Conc.
Sawcut & Match Exist. Pavement

Sta 19+20.00 Lt.
Install 1-Type 2 Inlet
Top=112.20
FL(S)=108.61
FL 4"(N)=109.20

Sta 19+20.00 18.70' Lt.
Install 1-5' ø RCMH
Top=112.30
FL(W)=107.30
FL(E)=107.30
FL(N)=108.55

Construct 24' Concrete Drive Approach (Sheet CV 4.9)
775 S.F. 8" Reinf. Conc.

BL Sta 15+37.20 38.10' Lt. Light Fixture

BL Sta 16+67.18 29.93' Lt. Light Fixture

BL Sta 17+84.59 38.10' Lt. Light Fixture

BL Sta 18+67.83 38.10' Lt. Light Fixture

BL Sta 19+50.90 37.70' Lt. Light Fixture

KGE MH. See note 1 Sheet CV 1.1

Construction Limits

Sta 16+04.95 40.59' Rt.
Adjust MH Top
Top=112.76
Replace KGE MH Lid w/ City of Wichita MH Lid

BL Sta 16+34.27 37.70' Rt. Light Fixture

Sta 17+00.00 Douglas= Sta 55+00.00 Handley

54+51.00 Sawcut & Match Exist. Pavement.

Sta 17+23.12 40.59' Rt.
Adjust MH Top
Top=112.27
Replace KGE MH Lid w/ City of Wichita MH Lid

BL Sta 15+57.19 37.70' Rt. Light Fixture

BL Sta 17+15.33 38.10' Rt. Light Fixture

BL Sta 17+34.00 29.95' Rt. Light Fixture

BL Sta 18+45.33 38.10' Rt. Light Fixture

BL Sta 18+80.33 38.10' Rt. Light Fixture

Sta 18+51.95 40.95' Rt.
No Adjusting Required
Replace KGE MH Lid w/ City of Wichita MH Lid

Sta 19+66.56 40.54' Rt.
Adjust MH Top
Top=112.70
Replace KGE MH Lid w/ City of Wichita MH Lid

Construct 22' Concrete Drive Approach (Sheet CV 4.9)
714 S.F. 8" Reinf. Conc.

-0.20% Lt. Curb
-0.10% CL
-1.40% CL
-0.20% Rt. Curb
+0.97% CL
-0.0% CL
+0.20% Rt. Curb
-0.25% Rt. Curb
-0.27% CL
-0.64% CL

Remove

Mill and Overlay

Concrete Intersection Pavement See Detail Sheet CV 1.7

6" Asphalt Pavement See Detail Sheet CV 1.7

* Offset dimension for inlets are measured from the inside face of the box structure nearest the curb to the centerline of the street right of way

kemiller engineering
516 S. Market,
Wichita, KS 67202
316/264-0242

CITY OF WICHITA

McCLUGGAGE VAN SICKLE & PERRY
ARCHITECTS PLANNERS LANDSCAPE ARCHITECTS
125 S. WASHINGTON WICHITA, KANSAS 67202
P.O. BOX 3545 WICHITA, KANSAS 67201
PH. 316/262-2345 FAX 316/262-2465

WEST DOUGLAS STREETSCAPE
ARKANSAS RIVER TO SENECA
WICHITA, KANSAS

PROJECT NO. 472 83608 OCA: 706846
MVP PROJECT NO. 101008
DATE: August 7, 2002
REVISED: August 30, 2002

SHEET
CV 1.2

PAVING PLAN 2