Scale: 1" = 20' Horz.
1" = 5' Vert.

GREENDALE ACRES — GREENDALE — ACRES — GREEN ACRES — FAULDERS — HARRY

Sta. 0+70.2 Line 1A
Construct Std. Type 1A Inlet
(L=11'4", W=4'4")
Elev.= 144.60 Top

Existing Concrete Pavement w/ Monolithic Curbs

Baseline = CL Harry

Remove & replace 6" conc. driveway pavement as necessary (TYP.)

Saw, Remove and replace 8" Reinf. Conc. pavement as necessary

LINE 1A - 18" RCP (See Sheet 14)

Sta. 5+78.3 Construct Std. Reinf. Conc. Manhole (See Detail Sheet, Sht 21) Elev.= 138.65 Top

Remove and Replace 5' concrete walk

LINE 1 - 54" RCP

Sta. 10+90.0
Construct Reinf. Conc. Manhole
(See Detail Sheet, Sht 21)
Elev.= 145.60 Top
(= Sta. 0+00, Line 1A)

Sta. 0+41.8 Line 1A
Construct Std. Type 1A Inlet
(L=11'4", W=4'4")
Elev.= 144.62 Top

BLOCK 4
PURCELL'S SEVENTH ADDITION

Existing Top Curb

507.6
511.1 LF 54" RCP @ +1.00%

LINE 1

Harry and Edgemoor Intersection Improvements

STORM SEWER LINE 1

Sta. 5+78.30 to 10+90.00

BAUGHMAN COMPANY P.A.
ENGINEERING & SURVEYING
316/262-7271 • 316 ELLIS • WICHITA, KANSAS 67211

PROJECT NUMBER	SHEET
468-82138 & 472-82668	9 OF 38

DESIGN	DRAWN	UTIL. CHECK'D	DATE	SCALE
T.C.R.	Sonny	T.C.R.	10-21-92	1" = 20'

REVISED 8-23-95 JKB