EXCEPTION

DILLON 8TH ADDITION

Scale: 1" = 20' Horz.
1" = 5' Vert.

Sta 0+00 Line 2 = Sta. 17+46.4 Line 1; Std. Reinf. Concrete MH Top Elev = 145.65 (See Sheet 11)

Sta. 0+11.2 Line 2B Construct Std. Type 1 Inlet (L=6'4", W=4'4") Elev.= 147.35 Top Remove & Replace parking lot curb and gutter to exist joints.

CAUTION: Monitor Well

Sta. 0+68.4 Construct Std. Type 1 Inlet (L=6'4", W= 6'4") Elev.= 145.80 Top

Sta. 1+47.9 Construct Std. Type 1 Inlet (L=11'4", W=6'4") Elev.= 146.36 Top (= Sta. 0+00 Line 2A & 2B)

Remove concrete driveways and sidewalk. See paving plan sheet.

Sta. 2+66.1 Construct Std. Type 1 Inlet (L=11'4", W=5'4") Elev.= 147.03 Top (= Sta. 0+00 Line 2C)

Sta. 4+98.3 Construct Std. Type 1A Inlet (L=11'4", W=5'4") Elev.= 148.12 Top (= Sta. 0+00 Line 2D)

Sta. 5+89.5 Construct Std. Type 1A Inlet (L=11'4", W=5'4") Elev.= 148.75 Top (= Sta. 0+00 Line 2E)

LINE 2

LINE 1

LINE 2B - 18" RCP (See Sheet 14)

LINE 2A - 18" RCP (See Sheet 15)

LINE 2C - 18" RCP (See Sheet 15)

LINE 2D - 18" RCP (See Sheet 15)

LINE 2E - 18" RCP (See Sheet 15)

231.48'

91.21'

10' Utility & Drainage Esmt by separate Instrument

28.55'

46.97'

79.52'

118.15'

155'

69.98'

231.55'

87.92'

36" RCP

30" RCP

24" RCP

18" RCP

CAUTION: 8" VCP Sanitary Sewer

Power Poles (2) to be relocated by KG&E

See pavement plans for sidewalk & pavement removal and replacement.

Power Poles (3) to be relocated by KG&E

Saw, Remove & replace 6" reinf. conc. pavement as necessary.

Power pole to be relocated by KG&E

CAUTION: 8" Water Main

Remove & replace 4" concrete walk as necessary

Saw, Remove & replace 6" reinf. conc. pavement as necessary.

Underground Cable to be relocated by SW Bell

Wheelchair Ramps Constructed By Others

Sta. 0+66.0 Line 2A Construct Std. Type 1 Inlet (L=6'4", W= 4'4") Elev.= 146.69 Top

Sta. 59.3 Line 2C Construct Std. Type 1 Inlet (L=11'4", W=4'4") L=6'4" W=6'4" Elev.= 147.20 Top

Sta. 0+46.2 Line 2D Construct Std. Type 1 Inlet (L=11'4", W=4'4") Elev.= 148.06 Top

Sta. 0+46.2 Line 2E Construct Std. Type 1 Inlet (L=11'4", W=4'4") Elev.= 148.43 Top

CAUTION!!! Existing 8" Water Line

CAUTION!!! Existing 8" Water Line

CAUTION!!! Existing 8" Water Line

REPLAT OF BLOCK 8 PURCELL'S SIXTH ADDITION

REPLAT OF BLOCK 8 PURCELL'S SIXTH ADDITION

EDGEMOOR

HARRY

Alley

8" Sanitary Sewer

8" Water

3" Steel KPL Gas

Gas Serv.

Water Serv.

Proposed Top of Curb

68.4 LF 36" RCP @ +0.30%

79.5 LF 36" RCP @ +0.30%

118.2 LF 30" RCP @ +0.30%

232.2 LF 24" RCP @ +0.30%

91.2 LF 24" RCP @ +0.30%

LINE 2

Harry and Edgemoor Intersection Improvements

STORM SEWER LINE 2

Sta 0+00 to 5+8914

BAUGHMAN COMPANY P.A.
ENGINEERING & SURVEYING
316/262-7271 • 315 ELLIS • WICHITA, KANSAS 67211

PROJECT NUMBER 468-82138 & 472-82668

SHEET 12 OF 38

DESIGN	DRAWN	UTIL. CHECK'D	DATE	SCALE
T.C.R.	Sonny	T.C.R.	10-22-92	1" = 20'

REVISED 8-23-95 JKB