FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87N-0127-01	1999	13	90

DATE	BY	
		REFERENCES NOTED
		REFERENCES CHECKED

SCALE
5 0 5 10
PLAN: Lat. & Long. (meters)

SRB

STA. 10+850.00, CL TO 10 000 LT, INSTALL 100mm C-900 IRRIGATION SLEEVE BELOW PAVEMENT SUBGRADE. 100mm CAP ON ENDS & MARK WITH 25mm PVC PIPE PROTUDING 500mm FROM FINISHED GRADE.

WESTLINK VILLAGE EIGHTEENTH ADDITION

OAK CLIFF ESTATES 3RD ADDITION

31

24

RESERVE "A" (Drainage)

CONSTRUCTION LIMITS

10.00m

10.00m

REMOVE CHAINLINK FENCE TO RIGHT-OF-WAY

STA. 10+804.34, 1 325 LT. & RT. BC, CONSTRUCT MEDIAN CURB AND GUTTER
STA. 10+804.34, 1 325 RAD BC CONSTRUCT MOUNTABLE MEDIAN NOSE

REMOVE TREES AS NEEDED FOR CONSTRUCTION

REMOVE EXISTING CONCRETE BOX AND HEADWALLS

REMOVE TREES AS NEEDED FOR CONSTRUCTION

STA. 10+897.20, 1 325 LT. & RT. BC, END MEDIAN CURB AND GUTTER
STA. 10+897.20, 1 325 RAD BC, CONSTRUCT MOUNTABLE MEDIAN NOSE

R/W

Trees

PROPOSED 1.5 m SIDEWALK

NW Cor., NE 1/4, Sec.30, Twp. 27-S, Range 1-W

℄ MAPLE ST.

10+750

10+800

10+850

10+900

90°00"

7.30m

6.94m

14.24m

23.6m

1.30m

1.2m

SHEFFORD ℄

SIDEWALK STATIONS (TYPICAL)

R9.00m

PLACE 48.8 m TYPE B CONCRETE SAFETY BARRIER WITH TERMINAL TRANSITIONS ON EACH END (KDOT STD. NO. 622 A) ALONG TEMPORARY ROAD ADJACENT TO BOX CULVERT CONSTRUCTION.

CONSTRUCT RCBC WITH THIS PROJECT SEE SHEET 24 OF 89

CONSTRUCT FULL HEIGHT CURB AND GUTTER (150mm) ALONG BOTH SIDES

CONSTRUCT 100mm TEMPORARY ASPHALT PAVEMENT WITH TYPE 'B' COMPACTION AND 2% - 4% CROSS-SLOPE TO SOUTH. MATCH EXISTING PAVEMENT.

5 WEST MILLBROOK SECOND ADDITION

1

RESERVE "B" (Drainage)

31

STA. 10+747.75 ℄
-1.296%
STA. 10+761.47 PT
+0.467%
STA. 10+765 PVI ELEV. 405.77 V.C.
+0.467%

MAPLE ST. IMPROVEMENTS - 119TH ST. W. TO MAIZE RD.
PAVING PLANS STA 10+750 TO 10+900

SRB
924 NORTH MAIN
WICHITA, KANSAS 67203
316-264-8008
FAX 264-4621
http://www.feist.com/~srb
E-Mail: srb@feist.com

SAVOY, RUGGLES & BOHM, P.A.
ENGINEERING & SURVEYING

PROJECT NUMBER
472-76-245-83053-000-000-001

DRAWN	DESIGN	REVIEW	DATE	UTILITY	SRB JOB
Staff	Staff		6-13-00		1218T

REVISED

13
90

DWG FILE: 1218.dwg