FHWA REGION NO.	STATE	PROJECT NUMBER	FISCAL YEAR	SHEET NUMBER	TOTAL SHEETS
7	KANSAS	87N-0127-01	1999	50	90

DATE	BY
REFERENCES NOTED	
REFERENCES CHECKED	

Sta. 9+928.60, 13.70 m Lt. Install Junction Box

50 mm Rigid Galvanized Conduit (Typical)

Sta. 10+069.14, 11.09 m Lt. Install Junction Box

Sta. 10+119.14, 10.71 m Lt. Install Junction Box

Sta. 10+169.14, 10.75 m Lt. Install Junction Box

Sta. 10+219.14, 10.79 m Lt. Install Junction Box

Sta. 10+269.14, 10.83 m Lt. Install Junction Box

Sta. 10+319.14 10.87 m Lt. Install Junction Box

Sta. 10+369.14, 10.29 m Lt. Install Junction Box

Sta. 10+419.14, 10.29 m Lt. Install Junction Box

Sta. 10+469.14, 10.28 m Lt. Install Junction Box

Sta. 10+519.14, 10.28 m Lt. Install Junction Box

Sta. 10+569.14, 10.27 m Lt. Install Junction Box

Sta. 10+619.14, 10.27 m Lt. Install Junction Box

Sta. 10+669.14, 10.27 m Lt. Install Junction Box

Sta. 10+719.14, 10.26 m Lt. Install Junction Box

119TH ST. WEST

MAPLE

PARKRIDGE

SHEFFORD

CEDAR CREST

PARKRIDGE ROAD

WESTLINK VILLAGE EIGHTEENTH ADDITION

WEST MILLBROOK ADDITION

MILLBROOK ESTATES

WEST MILLBROOK SECOND ADDITION

WEST MILLBROOK THIRD ADDITION

SCALE

10 0 10 20

PLAN: Lat. & Long. (meters)

MAPLE ST. IMPROVEMENTS - 119TH ST. W. TO MAIZE RD.
SIGNAL INTERCONNECTION PLAN

SRB
924 NORTH MAIN
WICHITA, KANSAS 67203
316-264-8008
FAX 264-4621
http://www.feist.com/~srb
E-Mail: srb@feist.com

SAVOY, RUGGLES & BOHM, P. A.
ENGINEERING & SURVEYING

PROJECT NUMBER
472-76-245-83053-000-000-001

DRAWN	DESIGN	REVIEW	DATE	UTILITY	SRB JOB
Staff	Staff		2-25-2000		1216T

REVISED

DWG NO. sig_cable01.dwg

SHEET 50

TOTAL SHEETS 90