



### DRAINAGE DATA TABLE

BASIN	English (U.S.) $Q = *CIA$												Metric (S.I.)						Storm Sewer	
	AREA (acre)	Tc (min)	I <sub>s</sub> (in)	I <sub>100</sub> (in)	Q <sub>s</sub> (cfs)	Q <sub>100</sub> (cfs)	CUM. AREA (acre)	Tc <sub>sys</sub> (min)	I <sub>s</sub> (in)	I <sub>100</sub> (in)	Q <sub>s</sub> (cfs)	Q <sub>100</sub> (cfs)	AREA (hectare)	Q <sub>s</sub> (cms)	Q <sub>100</sub> (cms)	CUM. AREA (hectare)	Q <sub>s</sub> (cms)	Q <sub>100</sub> (cms)	INLET (length)	PIPE (diameter)
A	1.28	15	4.56	7.37	4.7	7.6	4.18	15	4.56	7.37	15.3	24.7	0.52	0.13	0.22	1.70	0.43	0.70	1525 mm	900 mm RCP
B	1.28	15	4.56	7.37	4.7	7.6	2.90	15	4.56	7.37	10.6	17.1	0.52	0.13	0.22	1.18	0.30	0.48	1525 mm	750 mm RCP
C	0.81	15	4.56	7.37	3.0	4.8	1.62	15	4.56	7.37	5.9	9.6	0.33	0.08	0.14	0.66	0.17	0.27	1525 mm	750 mm RCP
D	0.81	15	4.56	7.37	3.0	4.8	0.81	15	4.56	7.37	3.0	4.8	0.33	0.08	0.14	0.33	0.08	0.14	1525 mm	600 mm RCP
E	0.73	15	4.56	7.37	2.7	4.3	1.46	15	4.56	7.37	5.4	8.6	0.30	0.08	0.12	0.60	0.16	0.24	1525 mm	750 mm RCP
F	0.73	15	4.56	7.37	2.7	4.3	0.73	15	4.56	7.37	2.7	4.3	0.30	0.08	0.12	0.30	0.08	0.12	1525 mm	600 mm RCP
G	0.66	15	4.56	7.37	2.4	3.9	1.32	15	4.56	7.37	4.8	7.8	0.27	0.07	0.11	0.54	0.14	0.22	3050 mm	750 mm RCP
H	0.66	15	4.56	7.37	2.4	3.9	0.66	15	4.56	7.37	2.4	3.9	0.27	0.07	0.11	0.27	0.07	0.11	3050 mm	450 mm RCP
I	134	23	-	-	-	213	-	-	-	-	-	213	54.23	-	6.03	54.23	-	6.03	-	2440 mm x 1220 mm RCBC

\* C<sub>s</sub> = 0.80 C<sub>100</sub> = 0.80



DATE	
BY	
REFERENCES NOTED	
REFERENCES CHECKED	



**MAPLE ST. IMPROVEMENTS - 119TH ST. W. TO MAIZE RD.  
DRAINAGE MAP (Sta. 0+000 to Sta. 0+790.3)**

**SRB** 924 NORTH MAIN 318-284-8008  
WICHITA, KANSAS 67203 FAX 318-284-4821  
http://www.srb.com/~srb E-Mail: srbs@srbs.com

**SAVOY, RUGGLES & BOHM, P.A.  
ENGINEERING & SURVEYING**

PROJECT NUMBER  
**472-76-245-83053-000-000-001**

DRAWN	DESIGN	REVIEW	DATE	TITLE	DRG. JOB
Staff	Staff		2-25-2000		1216T

57  
90