



TYPICAL SECTIONS OF GRADIENT TERRACES


| Slope % | Vertical Interval (Millimeters) | Horizontal Spacing (Meters) |
|---------|---------------------------------|-----------------------------|
| 1 | 800 | 81 |
| 2 | 1,000 | 50 |
| 3 | 1,200 | 40 |
| 4 | 1,400 | 35 |
| 5 | 1,600 | 32 |
| 6 | 1,800 | 30 |
| 7 | 2,000 | 29 |
| 8 | 2,200 | 27 |



TYPICAL SECTION OF OUTLET DITCH



PLAN



PROFILE

TEMPORARY SEDIMENT BASIN

| Drainage Area above Dt./Hectares | Value of "W" for various % of Ditch Grades | | | | | |
|----------------------------------|--|-------|-------|-------|-------|-------|
| | 3% | 4% | 5% | 6% | 7% | 8% |
| 1-2 | 2 400 | 2 400 | 2 400 | 2 400 | 3 600 | 4 200 |
| 2-3 | 2 400 | 2 400 | 2 400 | 3 000 | 3 600 | 4 800 |
| 3-4 | 2 400 | 2 400 | 2 400 | 3 000 | 3 600 | 4 800 |
| 4-6 | 2 400 | 2 400 | 2 400 | 3 000 | 4 200 | 5 400 |
| 6-7 | 2 400 | 2 400 | 2 400 | 3 600 | 4 200 | 6 000 |
| 7-8 | 2 400 | 2 400 | 2 400 | 3 600 | 4 200 | 7 200 |

NOTES:

- 1) Temporary Sediment Basins shall be constructed at locations as directed by the Engineer. All work and materials necessary for the construction of Temporary Sediment Basins shall be paid for as the bid item "Temporary Sediment Basin". The 450 mm x 11.0 m overflow pipe will be SUBSIDIARY to the bid item "Temporary Sediment Basin". The Temporary Sediment Basins shall be removed by District forces after seeding has been established if desired by the respective land owners.
- 2) Lengths and top elevations shall be determined in the field by the Engineer.

GENERAL NOTE

Terraces generally will not be required where the slope of the area is less than 3 percent. They shall be constructed on areas or portions of areas as designated by the Engineer.

Terraces shall be made as nearly parallel as practicable. Gradients for terraces shall vary from 0.1 percent at upper end to 0.4 percent at lower end or a uniform grade may be used.

Outlet ditches shall be constructed at locations best suited to empty into a natural stream bed, or if this is not possible, into a road ditch or channel where erosion can be minimized.

NOTE:
All dimensions are approximate.

| | | | | |
|-----|----------|--------------------------------------|-----|-------|
| 4 | 12/05/97 | Revised Pipe Size at Temp. Sed. Bas. | WCL | RDR |
| 3 | 3/17/97 | Revised Note for Temp. Sed. Basin | WCL | RDR |
| 2 | 7-5-95 | Convert to SI | WCL | RDR |
| 1 | 2-14-95 | Revised Note for Temp. Sed. Basin | WCL | RDR |
| NO. | DATE | REVISIONS | BY | APP'D |

KANSAS DEPARTMENT OF TRANSPORTATION

TEMPORARY PROJECT WATER POLLUTION CONTROL (SOIL EROSION)

LA852B SI

| | | | |
|-------------------|----------|------------|-----------------|
| F.H.W.A. APPROVAL | 12/16/97 | APP'D | Richard D. Ross |
| DESIGNED | WCL | DETAILED | HLH |
| QUANTITIES | TRACED | DAK | |
| DESIGN CK. | RDR | DETAIL CK. | RDR |
| QUAN. CK. | | TRACE CK. | WCL |

Drawn By: \$\$\$USERNAME\$\$\$
 DGN File: \$\$\$DGNFILE\$\$\$
 Plotted: \$\$\$SYTIME\$\$\$ View- PLOT 1