Fawn Grove

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
20+74	46.31	0.15				
			44.39	0.11	44.39	0.11
21+00	45.88	0.07				
			79.04	0.96	123.43	1.07
21+50	39.48	0.97				
			66.45	5.04	189.89	6.10
22+00	32.29	4.47				
			18.67	3.00	208.55	9.10
22+16	30.72	5.65				
			36.64	8.62	245.20	17.72
22+50	27.48	8.03				
			64.42	7.84	309.61	25.56
23+00	42.09	0.43				
			96.14	0.40	405.76	25.96
23+50	61.74	0.00				
			118.36	0.06	524.12	26.02
24+00	66.09	0.06				
			117.44	1.02	641.55	27.04
24+50	60.75	1.03				
			97.95	7.18	739.51	34.21
25+00	45.04	6.71				
			86.50	13.08	826.01	47.29
25+50	48.38	7.41				
			100.81	8.36	926.81	55.65
26+00	60.49	1.62				
			94.80	1.37	1021.62	57.02
26+42	61.40	0.13				
			0.00	0.00	1021.62	57.02

Smithmoor

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+00	19.03	13.06				
			8.78	4.42	8.78	4.42
0+10	28.37	10.82				
			86.69	11.07	95.46	15.49
0+60	65.25	1.13				
			69.21	6.94	164.68	22.43
1+00	28.18	8.24				
			8.79	4.45	173.47	26.88
1+10	19.28	15.79				
			26.62	6.06	200.08	32.95
1+30	52.58	0.57				
			0.00	0.00	200.08	32.95

Chateau Cir.

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+17	44.43	0.00				
			21.55	7.21	21.55	7.21
0+37	13.76	19.46				
			7.57	8.44	29.12	15.65
0+50	17.67	15.59				
			46.56	17.05	75.68	32.69
1+00	32.62	2.82				
			74.03	2.67	149.71	35.36
1+50	47.33	0.06				
			91.25	0.06	240.96	35.42
2+00	51.22	0.00				
			95.78	0.00	336.74	35.42
2+50	52.22	0.00				
			98.37	0.00	435.11	35.42
3+00	54.03	0.00				
			101.21	0.00	536.32	35.42
3+50	55.29	0.00				
			68.64	0.00	604.96	35.42
3+82.01	60.51	0.00				
			67.27	0.00	672.23	35.42
4+06.57	87.40	0.00				
			68.05	3.53	740.29	38.96
4+32.01	57.05	7.50				
			37.88	2.49	778.17	41.44
4+47.01	79.33	1.45				
			43.61	0.54	821.78	41.98
4+67.01	38.41	0.00				
			13.37	1.95	835.15	43.93
4+82.01	9.74	7.02				
			0.00	0.00	835.15	43.93

Smithmoor Cir.

STATION	AREAS Square Feet		VOLUMES Cubic Yards		CUMULATIVE VOLUMES Cubic Yards	
	CUT	FILL	CUT	FILL	CUT	FILL
0+17	73.61	0.00				
			48.41	0.00	48.41	0.00
0+37	57.09	0.00				
			27.44	0.00	75.85	0.00
0+50	56.91	0.00				
			107.70	0.00	183.55	0.00
1+00	59.41	0.00				
			115.28	0.00	298.83	0.00
1+50	65.09	0.00				
			115.00	0.00	413.83	0.00
2+00	59.11	0.00				
			97.94	0.00	511.77	0.00
2+50	46.67	0.00				
			91.59	0.00	603.37	0.00
3+00	52.25	0.00				
			103.58	0.00	706.95	0.00
3+50	59.62	0.00				
			62.15	0.00	769.11	0.00
3+82.01	45.23	0.00				
			47.47	0.10	816.58	0.10
4+06.57	59.14	0.22				
			39.64	10.67	856.22	10.77
4+32.01	24.99	22.42				
			20.28	9.14	876.49	19.91
4+47.01	48.00	10.48				
			24.20	3.88	900.69	23.79
4+67.01	17.34	0.00				
			6.29	0.23	906.99	24.02
4+82.01	5.32	0.82				
			0.00	0.00	906.99	24.02

Brentwood South Addition, Paving Improvements

Fawn Grove/Smithmoor/Chateau

WICHITA, KANSAS

Ruggles & Bohm, P.A.
Engineering, Surveying, Land Planning
924 North Main
Wichita, Kansas 67203
www.rbkansas.com
(316) 264-8008
(316) 264-4621 fax
E-mail: info@rbkansas.com

DESIGN EJG
DRAWN RLS
REVIEW
UTILITY
DATE Oct. 25, 2005
DRAWING FILE
PROJECT NUMBER 472-84285
RB JOB
SHEET 31
OF 32