FHWA REG NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	SHEETS
7	KANSAS	87N 0064-01	1997	7	130

Sta. 49+31.14 Jewell, Construct Curb Inlet (Type II), 14.83' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top= 1288.37 Install 24" x 6' Storm Swr. (RCP)(N) See Sht. No. 38, 47

Sta. 49+32.73 Jewell, Construct Reinf. Conc. Manhole, 6.57' Rt. L=6'2", W=6'2" Manhole Top=1287.94 Install 30" x 74' Storm Swr. (RCP)(E) See Sht. No. 39, 47

Sta. 49+25.40 Jewell, Saw Cut & Match Exist. Pav't. Drill and Grout Deformed Tie Bar #5 x 24" @ 24" O.C. Cost is Subsidiary to Concrete Pavement (9" Uniform)(AE)(NRDJ)

Sta. 88+59.95 Seneca, Construct Curb Inlet (Type II), 29.68' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.97 Install 18" x 2' Storm Swr. (RCP)(N) See Sht. No. 38, 47

Sta. 49+37.50 Jewell, Construct Curb Inlet (Type II), 14.83' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top= 1288.10 Install 18" x 2' Storm Swr. (RCP)(W) See Sht. No. 38, 47

Sta. 49+21.59 Jewell, Construct Curb Inlet (Type II), 14.83' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1288.49 Install 18" x 2' Storm Swr. (RCP)(E) See Sht. No. 38, 47

Sta. 90+63.25 Seneca, Construct Curb Inlet (Type II), 29.68' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.67 Install 15" x 37' Storm Swr. (RCP)(E) See Sht. No. 38, 47

Saw Cut & Match Exist. Pav't. 49' Lt.

Sta. 87+66.42 Seneca, Replace Exist. Water Service Line and Relocate Exist. Water Meter. See Sht. No. 53

Sta. 88+66.31 Seneca, Construct Curb Inlet (Type II), 29.68' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.96 Install 18" x 38' Storm Swr. (RCP)(E) See Sht. No. 38, 47

Sta. 49+27.95 Jewell, Construct Curb Inlet (Type II), 14.83' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1288.32 Install 18" x 2' Storm Swr. (RCP)(E) See Sht. No. 38, 47

Sta. 49+34.32 Jewell, Construct Curb Inlet (Type II), 14.83' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1288.14 Install 24" x 19' Storm Swr. (RCP)(S) See Sht. No. 38, 47

Saw Cut & Match Exist. Pav't. 49' Lt.

Sta. 90+63.25 Seneca, Construct Reinf. Conc. Manhole, 11.50' Rt. L=6'2", W=8'6" Manhole Top=1286.49 Install 12.5 Sq.Ft. x 307' Storm Swr. (HERCP)(N) See Sht. No. 39, 48

Saw Cut & Match Exist. Pav't. 49' Lt.

Const. Limits=R/W

Const. Limits

4' Walk

6' Walk

50' R/W

30'R (Typ.)

See Sht. No. 53A

B/L Prop. Improvements

JEWELL

SENECA STREET

JEWELL Ct.

HOTMAR 2ND. ADD. 1 — Robert J. & B. Janelle Maxwell

FOTMAR ADD. — James L. Nungesser, Et Al

HOTMAR ADD. 1 — Taco Tico, Inc.

McABDEEL 2ND. ADD. 4 — Taco Tico, Inc.

Marie J. Renollet

Harold A. Kingsley

Dorothy Williams

James F. & Carolyn C. Gaston

SENECA HAVEN ADD 1

RENOLLET 3RD. ADD. 3

Sta. 89+88.14 Seneca, Replace Exist. Water Service Line and Relocate Exist. Water Meter. See Sht. No. 53

Sta. 91+99.04 Seneca, Replace Exist. Water Service Line.

Sta. 88+20.72 Seneca, Replace Exist. Water Service Line.

Sta. 88+66.31 Seneca, Construct Reinf. Conc. Manhole, 11.50' Rt. L=6'2", W=7'9" Manhole Top=1286.89 Install 10.0 Sq.Ft. x 41' Storm Swr. (HERCP)(N) See Sht. No. 39, 47

Sta. 88+66.31 Seneca, Construct Curb Inlet (Type II), 29.68' Rt. L=6'4-3/8", W=4'4-3/8" Inlet Top=1286.96 Install 15" x 15' Storm Swr. (RCP)(W) See Sht. No. 38, 47

Sta. 89+10.56 Seneca, Construct Reinf. Conc. Manhole, 11.50' Rt. L=6'2", W=8'6" Manhole Top=1286.80 Install 12.5 Sq.Ft. x 149' Storm Swr. (HERCP)(N) See Sht. No. 39, 47

Sta. 50+80.78 Jewell Ct., Construct Curb Inlet (Type II), 14.83' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.43 Install 15" x 6' Storm Swr. (RCP)(N) See Sht. No. 38, 47

Sta. 50+80.78 Jewell Ct., Construct Reinf. Conc. Manhole, 6.57' Rt. L=6'2", W=6'2" Manhole Top=1286.04 Install 18" x 64' Storm Swr. (RCP)(W) See Sht. No. 39, 48

Sta. 50+86.46 Jewell Ct., Saw Cut & Match Exist. Pav't. Drill and Grout Deformed Tie Bar #5 x 24" @ 24" O.C. Cost is Subsidiary to Concrete Pavement (9" Uniform)(AE)(NRDJ)

Sta. 50+80.78 Jewell Ct., Construct Curb Inlet (Type II), 14.83' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.42 Install 15" x 19' Storm Swr. (RCP)(S) See Sht. No. 38, 48

Saw Cut & Match Exist. Pav't. 49' Rt.

BM #10 "□" cut on the N.E. cor. Taco Tico sign base. Sta. 91+89.13 55.11' Lt. Elev.=1288.26

LEGEND

PAVEMENT, DRIVEWAY AND/OR SIDEWALK REMOVAL.

UTILITY OWNERS

W – City of Wichita Water & Sewer Department (316)268-4908
T – Southwestern Bell Telephone Co. 1-571-2115
E – Kansas Gas and Electric (316)832-3169 or 832-3180
CATV – Multimedia Cablevision (316)262-4270
SS – City of Wichita Water & Sewer Department (316)268-4908
SWS – City of Wichita Water & Sewer Department (316)268-4908

KANSAS DEPARTMENT OF TRANSPORTATION

SOUTH SENECA STREET 87+00 TO 92+00

PROJECT NO. 87N 0064-01 SEDGWICK CO.

MID-KANSAS ENGINEERING CONSULTANTS, INC.
WICHITA, KANSAS

DESIGNED BY:	GJA	CHECKED BY:	GJA
DRAWN BY:	WNJ	DATE: 8/95	SHEET 7 OF 130

94005E11

H:\CIVIL\SENECA\94005\PAVE\94005E11 Fri May 30 10:56:50 1997