FHWA REG NO.	STATE	PROJECT NO.	YEAR	SHEET NO.	SHEETS
7	KANSAS	87N 0064-01	1997	13	130

Sta. 49+27.95 Dora, Construct Reinf. Conc. Manhole, 7.82' Lt. L=6'2", W=6'2" Manhole Top=1286.71 Install 30" x 71' Storm Swr. (RCP)(E) See Sht. No. 39, 50

Sta. 49+27.95 Dora, Construct Curb Inlet (Type II), 14.83' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1287.24 Install 18" x 2' Storm Swr. (RCP)(E) See Sht. No. 38, 49

Sta. 104+58.01 Seneca, Construct Curb Inlet (Type II), 29.68' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.60 Install 18" x 2' Storm Swr. (RCP)(S) See Sht. No. 38, 49

Sta. 104+64.37 Seneca, Construct Curb Inlet (Type II), 29.68' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.62 Install 18" x 2' Storm Swr. (RCP)(S) See Sht. No. 38, 49

Sta. 49+22.27 Dora, Saw Cut & Match Exist. Pav't. Drill and Grout Deformed Tie Bar #5 x 24" @ 24" O.C. Cost is Subsidiary to Concrete Pavement (9" Uniform)(AE)(NRDJ)

Sta. 104+51.65 Seneca, Construct Curb Inlet (Type II), 29.68' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.59 Install 36" x 37' Storm Swr. (RCP)(E) See Sht. No. 38, 49

Sta. 104+75.74 Seneca, Construct Curb Inlet (Type II), 29.68' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.65 Install 36" x 35' Storm Swr. (RCP)(E) See Sht. No. 38, 49

Sta. 102+11.10 Seneca, Construct Manhole (Type B), 11.50' Rt. Stack on Top of 10' x 3' RCB Manhole Top=1287.16 See Sht. No. 40, 50, 53

Sta. 49+27.95 Dora, Construct Curb Inlet (Type II), 14.83' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1287.36 Install 18" x 2' Storm Swr. (RCP)(E) See Sht. No. 38, 49

Sta. 49+34.32 Dora, Construct Curb Inlet (Type II), 14.83' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1287.06 Install 18" x 4' Storm Swr. (RCP)(S) See Sht. No. 38, 49

Sta. 104+82.10 Seneca, Construct Curb Inlet (Type II), 29.68' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.66 Install 18" x 2' Storm Swr. (RCP)(S) See Sht. No. 38, 49

Sta. 49+34.32 Dora, Construct Curb Inlet (Type II), 14.83' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1287.11 Install 24" x 20' Storm Swr. (RCP)(N) See Sht. No. 38, 50

Sta. 104+88.47 Seneca, Construct Curb Inlet (Type II), 29.68' Lt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.68 Install 18" x 2' Storm Swr. (RCP)(S) See Sht. No. 38, 49

Sta. 103+10.39 Seneca, Relocate Exist. Water Meter. See Sht. No. 53

Sta. 102+24.87 Seneca, Replace Exist. Water Service Line and Relocate Exist. Water Meter. See Sht. No. 53

Sta. 102+78.72 Seneca, Replace Exist. Water Service Line and Relocate Exist. Water Meter. See Sht. No. 53

Sta. 103+53.76 Seneca, Replace Exist. Water Service Line and Relocate Exist. Water Meter. See Sht. No. 53

Sta. 104+62.16 Seneca, Replace Exist. Water Service Line and Relocate Exist. Water Meter. See Sht. No. 53

Sta. 105+91.14 Seneca, Replace Exist. Water Service Line and Relocate Exist. Water Meter. See Sht. No. 53

Sta. 106+20.95 Seneca, Replace Exist. Water Service Line and Relocate Exist. Water Meter. See Sht. No. 53

Sta. 102+11.10 Seneca, Construct Curb Inlet (Type II), 29.68' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1287.25 Install 15" x 13' Storm Swr. (RCP)(W) See Sht. No. 38, 50

Sta. 104+10.42 Seneca, Construct Manhole (Type B), 11.50' Rt. Stack on Top of 10' x 3' RCB Manhole Top=1286.56 See Sht. No. 40, 50, 53

Sta. 104+56.05 Seneca, Construct Curb Inlet (Type II), 29.68' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.60 Install 18" x 2' Storm Swr. (RCP)(S) See Sht. No. 38, 49

Sta. 104+75.92 Seneca, Construct Reinf. Conc. Manhole, 11.50' Rt. L=6'2", W=13'8" Manhole Top=1286.56 Install 10' x 3' x 743' (RCB) Storm Swr. (S) See Sht. No. 39, 43, 49

Sta. 104+28.54 Seneca, Construct Manhole (Type B), 11.50' Rt. Stack on Top of 10' x 3' RCB Manhole Top=1286.50 See Sht. No. 40, 49, 53

Sta. 104+49.69 Seneca, Construct Curb Inlet (Type II), 29.68' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.58 Install 36" x 14' Storm Swr. (RCP)(W) See Sht. No. 38, 49

Sta. 104+46.66 Seneca, Construct Manhole (Type B), 11.50' Rt. Stack on Top of 10' x 3' RCB Manhole Top=1286.49 See Sht. No. 40, 49, 53

Sta. 104+31.96 Seneca, Construct Curb Inlet (Type II), 29.68' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.58 Install 36" x 14' Storm Swr. (RCP)(W) See Sht. No. 38, 49

Sta. 104+38.32 Seneca, Construct Curb Inlet (Type II), 29.68' Rt. L=6'4-3/8", W=3'4-3/8" Inlet Top=1286.56 Install 18" x 2' Storm Swr. (RCP)(S) See Sht. No. 38, 49

BM #12 "□" Cut on top of curb North side of Dora. Sta. 104+16.34 74.18' Lt. Elev.=1287.35

UTILITY OWNERS

W – City of Wichita Water & Sewer Department (316)268-4908
T – Southwestern Bell Telephone Co. 1-571-2115
E – Kansas Gas and Electric (316)832-3169 or 832-3180
CATV – Multimedia Cablevision (316)262-4270
SS – City of Wichita Water & Sewer Department (316)268-4908
SWS – City of Wichita Water & Sewer Department (316)268-4908

LEGEND
PAVEMENT, DRIVEWAY AND/OR SIDEWALK REMOVAL.

KANSAS DEPARTMENT OF TRANSPORTATION

SOUTH SENECA STREET
102+00 TO 107+00

PROJECT NO. 87N 0064-01 SEDGWICK CO.

MID-KANSAS ENGINEERING CONSULTANTS, INC.
WICHITA, KANSAS

DESIGNED BY:	GJA	CHECKED BY:	GJA	
DRAWN BY:	WNJ	DATE: 8/95	SHEET 13 OF 130	

H:\CIVIL\SENECA\94005\PAVE\94005E14 Fri May 30 11:00:34 1997