HAWTHORNE THIRD ADDITION

N

SCALE: 1"=20'
20 10 0 20

NOTE:
TOP OF CURB ELEVATIONS SHOWN ARE FOR FULL CURB. CONSTRUCT CURB AND GUTTER AS NOTED.

NOTE:
CONTRACTOR TO COORDINATE TREE TRIMMING AND/OR REMOVAL, IF NECESSARY, WITH THE ENGINEER/OWNER. NO TREES SHALL BE REMOVED WITHOUT PRIOR APPROVAL OF THE ENGINEER/OWNER.

STA. 11+65.6, LINE 2=
ST. STA. 12+00.0, 17.67' LT.
PROP. TYPE 1A CURB INLET
CONST. PAVEMENT HOOKUP &
PAVEMENT UNDERDRAIN.
INSTALL INLET SEDIMENT BARRIER.
INLET TOP=1359.37

STA. 12+00.9, LINE 2=
ST. STA. 12+00.0, 17.67' RT.
PROP. TYPE 1A CURB INLET
CONST. PAVEMENT HOOKUP &
PAVEMENT UNDERDRAIN.
INSTALL INLET SEDIMENT BARRIER.
INLET TOP=1359.37

CONST. STD. WHEELCHAIR RAMP

EXIST. TREE PROTECTION FENCE TO BE MAINTAINED DURING CONSTRUCTION. CONTRACTOR TO RELOCATE IF NECESSARY FOR CONSTRUCTION.

CONST. 6" AC PAVEMENT W/5" CRUSHED ROCK BASE ON GEOGRID REINFORCEMENT

INSTALL 2-6" PVC SLEEVES 33 L.F. EACH

STA. 11+16.4, LINE 3=
ST. STA. 15+66.61, 17.67' LT.
PROP. TYPE 1A CURB INLET
CONST. PAVEMENT HOOKUP &
PAVEMENT UNDERDRAIN.
INSTALL INLET SEDIMENT BARRIER.
INLET TOP=1360.11

P.V.I. ELEV.=1360.00 (NO VC)

P.V.I. ELEV.=1359.51 (NO VC)

P.V.I. ELEV.=1359.21 45' VC

P.V.I. ELEV.=1361.04 45' VC

P.V.I. ELEV.=1359.2 45' VC

MATCH LINE

PROP. SWS 24" RCP

PROP. SWS 30" RCP

PROP. WALK

RES. "G"

EXIST. 8" SAN.

@ 20' D&U ESMT.

20' UTIL. ESMT.

FUTURE BOXTHORN

FUTURE 12" WTR.

64' R/W

34' F-F

25' B.S.

WILLIAMSGATE

FUTURE

C3

C4

MH TOP=1360.42
FL OUT (SW)=1350.90
FL IN (NE)=1351.00
FL IN (E)=1351.00

STA. 12+05.34 WILLIAMSGATE
INSTALL SUBDIVISION BENCHMARK
(NO. 8134-08 KANSAS BLUE PRINT)

CONST. COMB. CURB AND GUTTER, FULL (6 5/8")

MH TOP=1361.50
FL OUT (SW)=1351.42
FL IN (N)=1351.52

P.V.I. ELEV.=1361.04 45' VC

MH TOP=1361.70
FL OUT (S)=1351.76
FL IN (NW)=1351.86

STA. 15+57.59 WILLIAMSGATE
INSTALL SUBDIVISION BENCHMARK
(NO. 8134-08 KANSAS BLUE PRINT)

MH TOP=1360.79
FL OUT (SE)=1352.33
FL IN (NE)=1352.43
FL IN (SE)=1352.43

P.V.I. ELEV.=1360.00 (NO VC)

STA. 11+51.6, LINE 3=
ST. STA. 15+66.61, 17.67' RT.
PROP. TYPE 1A CURB INLET
CONST. PAVEMENT HOOKUP &
PAVEMENT UNDERDRAIN.
INSTALL INLET SEDIMENT BARRIER
INLET TOP=1360.11

= EXIST. TREE PROTECTION
= TREE REMOVAL

HAWTHORNE
THIRD ADDITION

MKEC ENGINEERING CONSULTANTS
411 N. WEBB ROAD
WICHITA, KS. 67206
316 - 684 - 9600

HAWTHORNE THIRD ADDITION
WILLIAMSGATE/CAMDEN CHASE PHASE
PROJECT NAME

PAVING PLANS
SHEET TITLE

DRK	MKEC	DRK
DESIGN BY:	DRAWN BY:	CHECKED BY:
OCTOBER 2004	02167	7 / 48
DATE	JOB NO.	SHEET/OF

H:\CIVIL\02167\DWG\PAV\WILLIAMSGATE\PH3\02167_E2