





Scale: 1" = 40'




EXISTING MARKING PLANS

Sign and post to be removed by contractor and salvaged. Material to be delivered to City of Wichita Central Maintenance Facility. This work shall not be paid for separately, but shall be considered incidental to "Traffic Signal Installation".



Scale: 1" = 40'



PROPOSED MARKING PLANS

GENERAL NOTES

Striping dimensions are from centerline of stripe to centerline of stripe.

All single line dimensions are to centerline of stripe.


All double line dimensions are to center of space between stripes. (See Detail)

Existing markings consistent with the proposed marking plan shall remain. Existing marking which conflict with the proposed marking plan shall be completely removed. Removal methods shall be approved by the Engineer. Removal of existing markings shall be subsidiary.

* All markings on Bituminous Pavement shall be Thermoplastic Pavement Marking except as noted below.

** All symbols and all markings on Concrete Pavement shall be Heat-fused Preformed Thermoplastic Pavement Marking.

Heat-fused Preformed Thermoplastic Pavement Marking placed over a joint line in concrete pavement shall be sliced and removed along the joint edges after placement.



DETAIL OF DOUBLE YELLOW STRIPING

SUMMARY OF PAVEMENT MARKINGS

ITEMS	TOTAL	UNITS
PAVEMENT MARKING (THERMOPLASTIC) (WHITE) (6")	-	LIN. FT.
PAVEMENT MARKING (THERMOPLASTIC) (YELLOW) (4")	890	LIN. FT.
PAVEMENT MARKING (THERMOPLASTIC) (YELLOW) (18")	83	LIN. FT.
PAVEMENT MARKING SYMBOL (THERMOPLASTIC) (WHITE LEFT ARROWS)	-	EACH
PAVEMENT MARKING (THERMOPLASTIC) (WHITE) (12")	492	LIN. FT.
PAVEMENT MARKING (THERMOPLASTIC) (WHITE) (24")	102	LIN. FT.

FOR INFORMATION ONLY - BID ITEM "PAVEMENT MARKING" IS PAID AS LUMP SUM.

① THE CONTRACTOR SHALL COORDINATE THE PLACEMENT OF THE 24" WHITE STOP BARS WITH THE TRAFFIC SIGNAL CONTRACTOR. THE 24" WHITE STOP BARS SHALL NOT BE PLACED UNTIL THE TRAFFIC SIGNAL IS INSTALLED AND FUNCTIONING.

No.	Revision	By	Date
CITY OF WICHITA, KANSAS JAMES L. ARMOUR, P.E. - CITY ENGINEER NEWMARKET SQUARE ENTRANCE AND MAIZE ROAD MARKING PLAN CITY OF WICHITA PROJECT NO. 472-84276 Professional Engineering Consultants, P.A. 303 S. TOPEKA • WICHITA, KANSAS 67202 316-262-2691 • FAX 316-262-3003			
Designed by	BER	Job No.	05354
Drawn by	SAW	Date	AUGUST 2005
			SH. 5 of 8