





# TYPICAL 37' B-B PAVEMENT DETAILS



STATE CURB  
MODIFIED TYPE I  
COMBINED CURB & GUTTER





COMBINED CURB & GUTTER




COMBINED ROLLER TYPE CURB & GUTTER

	0'	2'	4'	6'	8'	10'	12'	14'	16'	18'	19.5'
A: Top of Curbs to Top of Surface Lift	0.01	.05	0.11	0.18	0.24	0.30	0.36	0.43	0.49	-	-
B: Top of Curbs to Top of Asphaltic Concrete	0.17	0.22	0.28	0.33	0.40	0.47	0.53	0.59	0.65	-	-
C: Top of Curbs to Top of C.R. Subgrade	0.43	0.47	0.53	0.64	0.65	0.72	0.78	0.85	0.91	0.97	1.01



TRANSVERSE CONSTRUCTION JOINTS

Transverse construction joints shall be constructed in flexible base pavements at locations where pavement joints existing flexible base pavement as shown by the detail. All costs associated with the construction of the transverse joint shall be included in the bid price for square yards 5" ASPHALTIC CONCRETE (3" BITUMINOUS BASE).




SECTION A-A


**CRUSHED ROCK GRADATION REQUIREMENTS**  
Percent of Aggregate Retained

1 1/2" .....	0
3/4" .....	15-60
#4 .....	40-80
#10 .....	74-92
P-200 .....	4-12

NOTE: Place 4" PVC Perforated Pipe at all drainage sump locations.  
Cost of Underdrain System to be incidental to the Reinforced Crushed Rock Subgrade.  
Rock Quality Shall Be The Same As Specified For Course Aggregate For Asphalt Concrete Mixes.



PAVEMENT UNDERDRAIN DETAIL



(Min. 16 Perforations Per Lin. Ft. @ 1/4" Dia.)  
Perforations To Be on Bottom Half

### General Notes

FABRIC BASE REINFORCEMENT SHALL BE B X 1100 GEOGRID AS MANUFACTURED BY TENSAR CORPORATION OR APPROVED EQUAL. FABRIC BASE REINFORCEMENT SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS. CRUSHED ROCK SHALL BE UNIFORMLY GRADED FROM 1-1/2" MAXIMUM SIZE TO NOT MORE THAN 10% PASSING A NO. 200 SIEVE. ROCK QUALITY SHALL BE THE SAME AS SPECIFIED FOR COARSE AGGREGATE FOR CONCRETE MIXES.

ROCK BASE IS TO BE COMPACTED AND SMOOTHED WITH A STEEL FACED ROLLER PRIOR TO PLACEMENT OF ASPHALT. TACK COAT WILL NOT BE APPLIED TO ROCK BASE.

A TACK COAT OF EMULSIFIED ASPHALT (SC-1H OR CSS-1H) SHALL BE APPLIED AT AN APPROXIMATE RATE OF 0.05 GALLONS PER SQUARE YARD BETWEEN EACH LIFT OF ASPHALTIC MATERIAL.

BITUMINOUS BASE AND ASPHALTIC CONCRETE WEARING SURFACE SHALL BE PLACED WITH A LAYDOWN MACHINE HAVING AUTOMATIC CONTROLS FOR LINE AND GRADE.

CONSTRUCTION JOINTS IN EACH LIFT SHALL BE STAGGERED A MINIMUM DISTANCE OF ONE (1) FOOT FROM JOINTS IN PRECEDING LIFTS AND PLACED SO THAT A JOINT WILL BE CONSTRUCTED ON THE CENTERLINE OF THE TOP LIFT.

THE ASPHALTIC CONCRETE PAVEMENT BETWEEN THE COMBINED CURB AND GUTTER SHALL BE PAID AS SQUARE YARDS OF 5" ASPHALTIC CONCRETE (3" BITUMINOUS Base.)

Revised: 1-24-00, MCG

		<b>37' PAVEMENT</b> <b>5" ASPHALTIC CONC.</b> <b>W/ CRUSHED ROCK BASE</b>	
		JAMES L. ARMOUR, P.E., L.S. CIVIL ENGINEER	
PROJECT NUMBER 472-84476	DRAWING NUMBER 766122	DATE 4/7/00	DESIGNER JAMES L. ARMOUR
CITY ENGINEER'S OFFICE CITY HALL - SEVENTH FLOOR 455 NORTH MAIN STREET WICHITA, KS 67202 (316) 268-4501 (316) 268-4114 FAX		SHEET 3 OF 33	DESIGN DATE