N-387,207.3956, E-2,373,260.9063
Sta. 0+00.0
Proposed Precast Concrete MH (by others).
Plug and stake end of Pipe for future connection by others. See detail sheet no. 8

N-387,194.6961, E-2,373,103.5707
Sta. 1+57.7
Const. MH 1
Standard MH

CAUTION !!!
Buried Telephone (SBC)

CAUTION !!!
Prop. 8" Waterline (by others)

N-387,188.6777, E-2,372,752.5994
Sta. 5+08.7
Const. MH 2
Standard MH

SCALE:
PLAN: LAT. & LONG. 0 40 80
PROFILE: HORIZ. SAME AS ABOVE
VERT. 0 5

OAK CREEK
RESERVE A
Prop. 21" San. Sewer (by others)
RESERVE O
PARKWAY
RES. D
RES. E
Not Parallel
30' Util. Esmt.
10' Waterline Esmt.
Guard Rail
Wood fence
Ungrd. Tele. (SBC)
Ovhd. Elec. (Westar) & Cable TV (Cox)
Fiber Optic (SBC)
30'x85' Street R/W (Film 2862, Pg. 2294)
21ST STREET NORTH
Exist. 8" Gas (KGS)(Steel)
WM (rec. info.)
Sara Wire Fence
Remove and reset fence as required.
Install 157.7 L.F. 8" Pipe.
Remove and replace 17 L.F. Asphalt Pavement in kind.
Remove and replace 10 L.F. Asphalt Pavement in kind.
Install 351.0 L.F. 8" Pipe.

SEE SHEET NO. 3 & 4 FOR PLAT COORDINATES

MICHAEL W. McKEE
13944
12/19/05
KANSAS
PROFESSIONAL ENGINEER

SANITARY SEWER LINE NO. 1

Proposed MH (by others)
Top Elev.= 1361.8
MH 1
Top Elev.= 1364.8
Buried Telephone (SBC)
Prop. 8" Waterline
Top of Pipe= 1355.50
MH 2
Top Elev.= 1368.7
Top mound= 1364.8
10'
Proposed Ground (by others)
Existing Ground
E In= 1345.23
from Prop. 21" SS Pipe (N)
E Out= 1345.23
E In= 1355.23
157.7 L.F. 8" Pipe @ 0.90%
351.0 L.F. 8" Pipe @ 0.90%
Sta. 1+68 to Sta. 2+35 -
Place 67 L.F. of Excavatable Flowable Fill from top of pipe bedding to Elev.= 1361.8

1375 1370 1365 1360 1355 1350 1345 1340 1335

0+00 1+00 2+00 3+00 4+00 5+00

CHANGE ORDER #1

No.	Revision	By	Date
1	CHANGE ORDER #1 - SANITARY SEWER ALIGNMENT CHANGE	MDK	06/14/05

LATERAL 1, MAIN 16
OF THE FOUR MILE CREEK SEWER

SANITARY SEWER LINE NO. 1

JAMES L. ARMOUR, P.E. – ACTING CITY ENGINEER
CITY OF WICHITA PROJECT NO. 468-63584

Professional Engineering Consultants, P.A.
303 S. TOPEKA • WICHITA, KANSAS 67202
316 262-2691 • FAX 316 262-3009

Designed By	MDK	Job No.	35-04688-001
Drawn By	TLB	Date	January 2005

Sheet 5 of 18

PLAN: DATE | BY | CHECKED | CHECKED

PROFILE: DATE | BY | CHECKED | CHECKED

DSNR: MDK OPER: GSL SCALE: 1"=40.00
C:\2004\04688\001\04688-001-C-SSPP0100 1 06-14-2005 10:21:57 am