SIGNING QUANTITIES

TYPE	SIGN FACE DESCRIPTION	SIZE	INSTALL
D4-1	PARKING	30" X 24"	2
R1-2	YIELD	36" x 36"	4
R2-1	SPEED LIMIT (25)	24" x 30"	2
R6-1	ONE WAY	36" x 12"	4
R8-3a	NO PARKING	12" x 12"	8
W2-6	ROUNDABOUT	30" x 30"	4
W13-1	15 MPH	18" x 18"	4

BILL OF MATERIALS

ITEMS	TOTAL	UNITS
PLASTIC MARKING (8" WHITE)	81.1	LF
PLASTIC MARKING (12" WHITE)	85.2	LF
PLASTIC MARKING YIELD MARKERS	28	EA.
PLASTIC MARKING (4" YELLOW)	519.2	LF
PLASTIC MARKING (6" YELLOW)	60	LF
PLASTIC MARKING (8" YELLOW)	1057.2	LF

FOR INFORMATION ONLY

MARKING & SIGNING PLAN

NIMS STREET ROUNDABOUT @ STACKMAN DRIVE

SCALE: 1" = 20'-0"

NOTE: 20'0" Page Rotation

wdm architects
Wilson Darnell Mann P.A.
105 N. Washington Wichita, Kansas 67202
ph 316.262.4700 fx 316.262.0002


BAUGHMAN COMPANY P.A.
ENGINEERING, SURVEYING, & PLANNING
316-262-7271 • 333 BELLE • WICHITA, KANSAS 67211

JEFFREY F. BRAUN
LICENSED
15076
KANSAS
PROFESSIONAL ENGINEER

NIMS ROUNDABOUT
Central Riverside Park

Wichita, Kansas

KEY PLAN



CENTRAL RIVERSIDE PARK

PRINTS ISSUED
August 20, 2002

Baughman No. 00-08-E798
drawn: STAFF
checked: STAFF

NIMS STREET ROUNDABOUT — MARKING & SIGNING PLAN

SECTION THREE
9 of 22

© copyright 2002 Wilson Darnell Mann P.A.

Eng\Riverside\Sonny\Dwg\Marking.dwg