FONTANA

AN ADDITION TO WICHITA, SEDGWICK COUNTY, KANSAS

REPLATTED AS "FONTANA 2ND"

SCALE: 1" = 100'

• = 1/2" REBAR W/PEC CAP UNLESS OTHERWISE NOTED

MATCH LINE

MATCH LINE

= VACATED EASEMENTS
(FILM 2865, PAGE 6546 – RECORDED 3/16/05)

SEE FILM 2866, PAGE 8437
FOR NEW UTILITY EASEMENTS
SEE FILM 2866, PAGE 8438
FOR NEW WALL EASEMENT
SEE FILM 2866, PAGE 5921
FOR NEW RESERVES

RESERVE "C"

RESERVE "B"

RESERVE "F"

RESERVE "K"

RESERVE "L"

RESERVE "H"

RESERVE "G"

RESERVE "A"

MARK RANDAL

LANDON CIRCLE

CHAMBERS CIRCLE

COVINGTON CT.

CORTINA

SHEFFORD

119TH STREET WEST = SECTION LINE
Complete Access Control 763.04'
Access Control Complete Access Except One Opening 64.00'
Complete Access Control 130.00'

℄ 29TH STREET NORTH = SECTION LINE
Complete Access Control 563.32'
Access Control Except One Opening 100'
Complete Access Control 667.56'

30' Roadway Easement (Road Record Book C, Page 390)
60' Street Dedication

S.W. Cor. Sec. 31, Twp. 26S, R1W
Found Pipe w/ Sedgwick County
Cap in Concrete

S 1/4 Cor. Sec. 31, T26S, R1W
Found Stone & 3/4" IP on
West side

N00°30'19"E 634.74'

N88°49'04"E 1310.10'

N88°49'04"E 1851.45'

N88°49'04"E 1332.02'

N88°49'04"E 563.32'

N88°49'04"E 667.56'

CURVE DETAILS

(#) = CURVE NUMBER

(1) CURVE NO. 1
R=184.00'
Δ=34°31'37"
Δ=42°42'05"
R=216.00'

(2) CURVE NO. 2
L=30.41'
R=18.00'
Δ=96°48'23"

(3) CURVE NO. 3
L=26.86'
R=18.00'
Δ=85°30'24"

CURVE NO. 8 (8)
R=1984.00'
Δ=11°37'35"
R=2016.00'

CURVE NO. 9 (9)
R=84.00'
Δ=3°29'21"
R=116.00'

CURVE NO. 10 (10)
R=384.00'
Δ=20°54'54"
Δ=15°03'15"
R=416.00'

(4) CURVE NO. 4
R=134.00'
Δ=2°7'13"02"
R=166.00'

(5) CURVE NO. 5
R=1984.00'
Δ=12°20'13"
R=2016.00'

(6) CURVE NO. 6
R=84.00'
Δ=98°24'06"
R=116.00'

(7) CURVE NO. 7
R=84.00'
Δ=98°24'06"
R=116.00'

CURVE NO. 11 (11)
R=33.00'
Δ=60°28'20"

CURVE NO. 12 (12)
R=33.00'
Δ=60°28'20"

CURVE NO. 13 (13)
R=33.00'
Δ=60°28'20"

CURVE NO. 14 (14)
R=33.00'
Δ=60°28'20"

COORDINATE LIST

POINT	NORTH	EAST
1200	25260.5914	16692.7768
1201	25258.5283	16592.7980
1202	25358.5071	16590.7350
1205	25742.9056	16379.9230
1206	25636.9108	16262.3501
1207	25541.7677	16250.4803
1208	25621.9313	16382.4193
1209	25532.9781	16320.9342
1210	25461.9932	16322.3989
1211	25462.8720	16355.2963
1212	25434.5185	16396.6168
1213	25404.6844	16356.4929
1214	25404.0055	16323.5955
1215	25548.9479	16192.9265
1216	25644.0910	16204.7963
1217	25800.8932	16378.7265
1219	25807.1409	16681.4988
1220	25791.7347	15934.8887
1221	26022.6124	16645.0713
1222	26077.0410	16625.0077
1236	25884.7688	15954.0232
1237	25856.2967	16004.5538
1238	25823.1933	15851.1022

POINT	NORTH	EAST
1239	25765.2056	15852.2988
1240	25944.1675	15848.6060
1241	25821.0553	15747.4897
1242	25763.0676	15748.6863
1243	25791.2211	15707.3658
1253	26057.7174	16264.8285
1254	26217.4787	15816.4399
1255	26236.9454	15761.8043
1256	26182.3993	15742.3695
1257	26162.9328	15797.0051
1258	26134.2978	15758.0187
1271	26101.0271	15081.8907
1272	26103.5781	14792.5742
1273	26167.5756	14793.1384
1274	26165.0246	15082.4550
1405	26044.7705	16702.0999
1406	26087.1138	16739.2893
1407	26119.1940	16733.4975
1408	26089.3664	16745.0868
1409	25917.8575	16811.7255
1410	26118.8716	16890.7781
1411	26096.9271	16854.0349
1412	26073.2236	16866.7996

POINT	NORTH	EAST
1413	26079.4094	16849.8959
1414	26064.4171	16897.6523
1415	26058.2312	16914.5560
1416	26075.5676	16919.3986
1418	26092.2479	17027.6094
1419	26060.2494	17027.3004
1420	26091.8489	17068.9445
1421	26059.8504	17068.6356
1422	25975.8543	17067.8248
1423	25987.6769	17183.5362
1424	25969.9328	17151.8158
1426	25565.9712	17195.9550
1427	25561.7479	17164.2350
1428	25550.6617	17080.9697
1429	25536.7876	17196.1370
1430	25532.8406	17228.9002
1431	25506.2781	17209.3187
1432	25466.0318	17179.6499
1433	25430.5761	17144.3953
1434	25407.1753	17121.1273
1435	25438.9541	17112.2333
1436	25434.6864	17083.3629
1437	25466.6796	17082.7027

POINT	NORTH	EAST
1438	25464.5301	16978.5356
1439	25432.5370	16979.1957
1440	25400.1880	16962.6279
1441	25433.0384	16965.7672
1442	25419.1097	16935.5914
1443	25548.5123	16976.8026
1444	25447.7790	16894.6271
1445	25482.1502	16858.3144
1446	25504.8353	16834.3480
1447	25514.5087	16865.8983
1448	25559.0653	16851.2836
1449	25556.1541	16893.1509
1450	25739.5583	14885.5108
1451	25985.3755	16854.2235
1452	25989.3403	16885.9770
1453	26005.9429	17018.9445
1454	26051.9931	16893.1058
1455	26062.9902	16863.0548
1459	25459.3523	16630.6630
1460	25747.9567	16624.7077
1461	25805.9443	16623.5111

× 1000 = COORDINATE POINT NO.

No.	Revision	By	Date

FONTANA ADDITION-PHASE 1

PLAT

JAMES L. ARMOUR, P.E.– CITY ENGINEER
CITY OF WICHITA PROJECT NO. 472-84086

Professional Engineering Consultants, P.A.
303 S. TOPEKA • WICHITA, KANSAS 67202
316-262-2691 • FAX 316-262-3003

Designed by	BDB, BLB	Job No.	35-04485-000
Drawn by	BJS	Date	September 2004

Sheet 4 of 101

Saved 03-13-2006 11:12:14 AM by BJS
Plot Scale 1:100 03-14-2006 11:10:49 AM by BJS
S:\2004\04485\000\Plat 4 of 7