



Sta. 50+00.00
N=1680945.59
E=1636585.25

Sta. 51+88.86 McCormick, 25.17' Lt.
Replace Exist. Frame and Lid. Adjust
Manhole Top. See Sht. 34

Sta. 50+61.48 McCormick, 26.10' Lt.
Replace Exist. Frame and Lid. Adjust
Manhole Top. See Sht. 34

Sta. 53+69.57 McCormick, 38.48' Lt.
Water Meter to be Adjusted by C.O.W.
Contractor to Coordinate work.

Sta. 54+62.42 McCormick, 26.45' Lt.
Replace Exist. Frame and Lid. Adjust
Manhole Top. See Sht. 34

STA: 50+00.00 Old McCormick Ave.
STA: 9+45.61 Sheridan

- Ctr. Sec. 25, T27S, R1W
"X" Cut on Sanitary Sewer Manhole Lid
- | | |
|---------------------------------------|-----------|
| 1. Nail and Cap in SW side Power Pole | 39.50' NW |
| 2. Chiseled "x" Top of Curb | 44.75' NW |
| 3. Ctr. Top of Fire Hydrant | 44.87' NE |
| 4. Nail and Cap in NW side Power Pole | 42.08' SW |
| 5. N=1680944.65, E=1636604.35 | |

UTILITIES

- | | |
|--|--------------|
| CATV - Cox Communications (Cable) | 262-0661 |
| E - Westar Energy (Electric) | 261-6512 |
| SWS - City of Wichita Stormwater Utility | 268-4071 |
| SS & W - City of Wichita Water Dept. | 262-6000 |
| T - SBC (Telephone) | 800-870-8390 |

KEY NOTES

- ① Utility pole to be Removed Prior to Construction
- ② Tree to be Removed Prior to Construction
- ③ Remove Sign and deliver to City. See general note.

LEGEND

- Drive, Pavement and/or Sidewalk Removal
- x 110.5 Spot Elevation
- Direction of Change
- 111 - Exist. Contour
- 111 - Prop. Contour



 MKEC ENGINEERING CONSULTANTS <small>411 N. WEBB ROAD WICHITA, KS. 67208 316-684-9600</small>	McCORMICK AVENUE STREET IMPROVEMENTS	
	<small>PROJECT NAME</small>	
McCORMICK		
<small>SHEET TITLE</small>		
<small>JRA</small> DESIGN BY.	<small>WNJ</small> DRAWN BY.	<small>KJS</small> CHECKED BY.
<small>AUGUST 2005</small> DATE	<small>03245</small> JOB NO.	<small>39A / 111</small> SHEET/OF