WATER VALVE BOX ELEVATIONS			
STREET	STATION	OFFSET	PROPOSED ELEVATION
OAK CREEK PARKWAY	@ S. Bd. 32+37.7	8.0' Lt.	1366.5
OAK CREEK PARKWAY	@ S. Bd. 32+64.3	9.0' Lt.	1366.9
OAK CREEK PARKWAY	@ S. Bd. 32+67.6	11.5' Lt.	1366.9
OAK CREEK PARKWAY	@ S. Bd. 32+69.4	9.0' Lt.	1366.9

SCALE: 1"=20'

+0.30' Wk. Gr. (R/W)

-3.04% T.C. Lt.

125.00' V.C.

+1.16% T.C. Lt.

75.00' V.C.

-1.32% T.C. Lt.

Prop. Top Valve Box Elev.=1366.9

Prop. Top Valve Box Elev.=1366.9

Prop. Top Valve Box Elev.=1366.5

Prop. FH Bury Line Elev.=1366.5

@ S. Bd. Sta. 31+37.01 Install "Flat Survey Marker No. 8134-08, 3" Top Diameter" Bench Mark Disc.

4" Concrete Sidewalk Pavement

5'-0"

Prop. 8" Water (by Others)

Prop. 6" Water (by Others)

Prop. 8" San. Sewer (by Others)

Prop. SS MH
Top Elev.=1366.6
℄ In=1359.41 (N)
℄ Out=1359.41 (E)

Prop. Top Valve Box Elev.=1366.9

Curve No. 11

Curve No. 10

Curve No. 9

Curve No. 8

Curve No. 7

Curve No. 6

Combined Curb & Gutter (6 5/8" & 1 1/2")

Const. Std. Type 1A Inlet Hookup See Sheet No. 33.

Median Curb & Gutter (6 5/8")

6" Asphaltic Concrete Pavement (4" Bituminous Base)

OAK CREEK PARKWAY

@ N. Bd. Sta. 27+52, 47.0' Lt. Install (2) 53 L.F. 4" Schedule 40 PVC Pipe Sleeves.

@ N. Bd. Sta. 30+86.3 to 31+40.0, 27.0' Lt. Install (2) 4" Schedule 40 PVC Pipe Sleeves. #

@ N. Bd. Sta. 31+67.3 to 32+15.8, 27.0' Lt. Install (2) 4" Schedule 40 PVC Pipe Sleeves. #

@ N. Bd. Sta. 32+40, 4.5' Rt. Install Traffic Signs (W2-6)(Roundabout) & (W13-1)(Advisory Speed) on Single Post. See Sheet No. 50.

-2.80% T.C. Rt.

+1.12% T.C. Rt.

100.00' V.C.

No V.C.

+2.12% T.C. Rt.

150.00' V.C.

-2.40% T.C. Rt.

+0.30' Wk. Gr. (R/W)

Sleeves to be 42" below top of curb. Each end of 4" PVC pipe sleeves shall be capped and marked with steel "T" posts or 2" dia. steel pipe a maximum of 12" above finished grade. Pipe, caps, markers, and installation thereof shall be Subsidiary to Median Comb. Curb & Gutter (6 5/8").

BRIAN D. BOUTWELL LICENSED PROFESSIONAL ENGINEER 10889

8/23/05

No.	Revision	By	Date

OAK CREEK – PHASE 1

OAK CREEK PARKWAY

@ N. Bd. STA. 27+25 TO STA. 33+00/@ S. Bd. STA. 28+25 TO STA. 33+50

JAMES L. ARMOUR, P.E.– CITY ENGINEER

CITY OF WICHITA PROJECT NO. 472-84209

Professional Engineering Consultants, P.A.

303 S. TOPEKA • WICHITA, KANSAS 67202

316-262-2691 • FAX 316-262-3003

Designed by	BDB, BLB	Job No.	35-04688-000
Drawn by	BJS	Date	October 2004

Sheet 9 of 86

DSN= BLB OPER= BJS SCALE: 1=20.00

Q:\2004\04688\000\04688-000-C-STR28-34 08-24-2005 12:19:35 am